June 1975

Environmental Monitoring Series

FOR QUALITY ASSURANCE PROGRAMS FOR MOBILE SOURCE EMISSIONS MEASUREMENT SYSTEMS:

PHASE IV, HEAVY-DUTY GASOLINE ENGINES TEST PROCEDURES



U.S. Environmental Protection Agency Office of Research and Development Washington, D. C. 20460

GUIDELINE DISTRIBUTION RECORD

EPA-650/4-75-024-h "Guidelines for Quality Assurance Programs for Mobile Source Emissions Measurements Systems: Phase IV, Heavy-Duty Gasoline Engines - Test Procedures"

The series of documents, "Guidelines for Quality Assurance Programs for Mobile Source Emissions Measurement Systems," have been prepared and issued in a revisable document-controlled format so that any future revisions or additions may be distributed to the Guideline users. Individual copy numbers have been assigned to each volume of the series. These numbers appear on this record sheet and on the title page of each document. The user of these documents must complete the "Distribution Record Card" and return it in the pre-addressed envelope to the address shown below so that automatic distribution for future revisions may be made directly to the user. Also, notice of any reassignment of the documents by number and title to other individuals (by name, address, and copy number) should be sent to the same address.

U.S. Environmental Protection Agency Office of Mobile Source Air Pollution Control 2565 Plymouth Road Ann Arbor, Michigan 48105

ATTN: Quality Assurance

COPY No. $__49$	î	
-------------------	---	--

(cut along dotted line)

			·	
		DISTRIBUTI	ON RECORD CARD	
Guidelin User	e			Date
	Last Name	First	Middle Initial	
		Title		
Address to Send				
Future Revision and	s	Street		•
Addition	s City	State	Zip Code	
If addre	ss is a firm	(fill in)		
	•		Firm	
Assur	ance Program	s for Mobile Sour	650/4-75-024-h "Guidel ce Emissions Measureme nes - Test Procedures"	ent Systems:
Please s	end me any r	evisions and addi	tions of this volume.	

GUIDELINES FOR QUALITY ASSURANCE PROGRAMS FOR MOBILE SOURCE EMISSIONS MEASUREMENT SYSTEMS:

PHASE IV, HEAVY-DUTY GASOLINE ENGINES --

by

Harold Wimette, Rod Pilkington, and Tom Kelly

Olson Laboratories, Inc. 421 East Cerritos Avenue Anaheim, California 92805

491

Contract No. 68-02-1740 ROAP No. 26BGC Program Element No. 1HA327

EPA Project Officers:

R. C. Rhodes
Quality Assurance and Environmental Monitoring Laboratory
Research Triangle Park, North Carolina 27711

and

C. Don Paulsell Office of Program Management Ann Arbor, Michigan 48105

Prepared for

U.S. ENVIRONMENTAL PROTECTION AGENCY
Office of Mobile Source Air Pollution Control

an d

Office of Research and Development Washington, D. C. 20460

June 1975

EPA REVIEW NOTICE

This volume has been prepared by Olson Laboratories, Incorporated consistent with the Environmental Protection Agency Quality Assurance principles and concepts and with the Environmental Protection Agency Mobile Source Testing Practices at Ann Arbor, Michigan.

The guidelines and procedures are generally applicable to mobile source testing operations and are intended for use by those engaged in such measurement programs

It is requested that recipients and users of this document submit any comments and suggestions to the Project Officers.

Mention of trade names or commercial products does not constitute Environmental Protection Agency endorsement or recommendation for use.

RESEARCH REPORTING SERIES

Research reports of the Office of Research and Development, U.S. Environmental Protection Agency, have been grouped into series. These broad categories were established to facilitate further development and application of environmental technology. Elimination of traditional grouping was consciously planned to foster technology transfer and maximum interface in related fields. These series are:

- 1. ENVIRONMENTAL HEALTH EFFECTS RESEARCH
- 2. ENVIRONMENTAL PROTECTION TECHNOLOGY
- 3. ECOLOGICAL RESEARCH
- 4. ENVIRONMENTAL MONITORING
- 5. SOCIOECONOMIC ENVIRONMENTAL STUDIES
- 6. SCIENTIFIC AND TECHNICAL ASSESSMENT REPORTS
- 9. MISCELLANEOUS

This report has been assigned to the ENVIRONMENTAL MONITORING series. This series describes research conducted to develop new or improved methods and instrumentation for the identification and quantification of environmental pollutants at the lowest conceivably significant concentrations. It also includes studies to determine the ambient concentrations of pollutants in the environment and/or the variance of pollutants as a function of time or meteorological factors.

This document is available to the public for sale through the National Technical Information Service, Springfield, Virginia 22161.

Publication No. EPA-650/4-75-024-h

INTRODUCTION

The test procedures contained in this volume are a documentation of the 1975 heavy-duty gasoline emission measurement test requirements presently in use at the Ann Arbor facility of the Environmental Protection Agency. These test procedures comply with Federal Regulations as stated in the Federal Register, (Subpart H). Refer to Section 3, of Volume I, for a listing of applicable Federal Register paragraphs.

Section 5, Volume I, outlines the development of an Operations manual which may be used as a guideline for a Quality Assurance program. A typical format of a test procedures manual is described and offers a guide for implementing and interpreting the test procedures contained in Volume II. A user may accept the manual in its presented form, or may modify the format to suit specific contractual obligations, or delete certain procedures which may not be performed at that facility. The user will be required to make revisions as needed to assure that the manual complies with Federal Regulations. Revisions may be implemented manually, by computer updates or by magnetic card storage.

For ease of use, the test procedures are separated into nine distinct sections, numbered 100-900. The table of contents shows the major heading of each section and the test procedures contained in each. To differentiate between the light-duty and heavy-duty testing which are both included in this contract, the test procedures are numbered to correspond to Light Duty, 101-149, 201-249, etc. and Heavy Duty, 150-199, 250-299, etc. Heavy-duty diesel procedures modified for use with heavy-duty gasoline engines are suffixed with a -G, e.g.TP-750-G. Certain procedures developed for Phase I and II (Light-Duty Gasoline Vehicle and Heavy-Duty Diesel Engine) are equally applicable to Phase IV (Heavy-Duty Gasoline Engines) and have been included in this volume, utilizing the original Test Procedure reference number allocated for Phase I and II.

To assist in defining the overall scope of the heavy-duty testing program, the tables from Section 3, Volume I, briefly outlining the test procedures, specifications, and quality provisions are included in the introduction to the test procedures manual.

This document details test procedures for heavy-duty gasoline engines. The test procedures for light-duty diesel (Phase III) appear as a supplement to the light-duty gasoline vehicle procedures detailed in Phase I, Volume II. Heavy-Duty Diesel Engine Test Procedures appear in Volume II of the Report for Phase II.

TABLE OF CONTENTS

		Page
INTROL	DUCTION	iii
TEST F	PROCEDURE SUMMARY	vii
		Effective
Section	<u>on</u>	Date(s)
100	GAS BLENDING, FUEL ANALYSIS AND INVENTORY	
101	Preparation of Binary Gas Mixture	
102	Calibration of Gas Mixtures	
200	CALIBRATION	
203	Gas Analyzer Calibration Curve Generation	
204	Chart Recorder Calibration	
205	Temperature Recorder Calibration	
206	Barometric Pressure Calibration and Correlation	
250	Engine Dynamometer Calibration	
300	VERIFICATION	
304	CO ₂ /H ₂ O Interference Check	
400	CORRELATION	
401	Analyzer Cross Check	
600	DAILY OPERATION	
601	Log Book Entries	
602	Drift/Noise/Gain/Tune	
700	EMISSION TESTING	
750-	G Receipt, Build-up and Installation of the Gasoline Test Engine	
757	Heavy Duty Gasoline Engine Dynamometer Test Cycle	
758	Heavy Duty Gasoline Engine Exhaust Analysis Procedure,	
750	CO, CO ₂ , HC, and NO ₂	
800	DATA VALIDATION	
850	Data Validation-Heavy Duty Testing	
900	PROGRAM PLANNING AND QUALITY AUDIT	

HEAVY DUTY GASOLINE ENGINE TEST PROCEDURE SUMMARY

PROCEDURE OR TASK	DRIEF DESCRIPTION	FR REF.	SPECIFICATION OR TOLERANCE-FED, REG.	SPECIFICATIONS	QUALITY PROVISIONS	TEST INVALID	CORRECTIVE ACTION	TRAINING OR SKILL LEVEL
1 Engine. Receiving Inspection	Engine shipped to the EPA from the manufacturer is inspected for damage and conformance to installation	FR. Vol. 40 2-27-75 85.774-29(a) TP 750-G	TOLLOWICE TED. REG.	SAE OR ENG. PRACT. MSAPC Advisory Circular ilo. 22A Appendix A. 4-23-73	Receiving Inspection check list	Failure to comply with specifications/ shipping damage	Contact engine manu- facture for dis- position of the engine.	Knowledge of engine installation require- ments/inspection procedures
2. Engine Installation	The engine and prealigned stand are installed in the test cell and attached to the dynamometer	85.774-11 35.774-16(a)(1) TP-750-G	Dynamometer capable of maintaining constant speed :100 RPM from full throttle to closed throttle motoring	MSAPC No. 22A	Installation check list/inspection by mfr. rep.	Incomplete/Improper installation	Correct Discrepancy	Mechanical skill and knowledge of engine/ dyno.
3. Engine/Dyno Check out	The engine is operated at idle and load conditions to check for proper operation. Engine parameters are checked against manufacturer's specifications	85.774-16(2) TP-750-G	Adjustments on engine are limited to unscheduled mainternance listed in Ref. Para.	SAE J8166-Engine test code	Calibration of engine analyzer	Incorrect Engine parameters	Adjust to mfr. specifications	Knowledge of dyno engine analyzer operation
4. Engine preconditioning	Start engine and pre- condition with one or more cycles, service accumulation or test cycle. Allow to soak prior to test	85.774-7,11,16 TP-757	Engine must reach normal operating conditions, soak time 1-2 hours temp., 60-86°F	Water/oil at equilibrium temp	Speed/torque/temp. trace, soak time checked by Data Yalidation	Out of limit soak time/ Temp/Cycle	Repeat precondi- tioning	Knowledge of engine/ dyno operation
5. Engine Test Cycle	An initial 5 minute idle, two warmup cycles, and two hot cycles constitute a complete Dyno Run	85.774-11,12,16 TP-757	Amb. Temp. 68-86 ⁰ F 2000± 100 RPM Idle - Mfr. spec.		Data validation Q.A. audit	Deviation of 2 sec. CT mode; 0.3 inc. Hg. cruise/PTD mode, 0.2 inc. Hg. PTA/FL Hode last 10 sec. of Hode. 200 RPM first 4 sec./100 RPH rest.	Repeat precondi- tioning and Test	As above
6. Sampling System	Comprised basically of 5 NDIR instruments, Sample pumps, refrigera- tion, flow controls and pressure and flow meters	35.775-13 TP-758	Instrument ranges LHC 0-1000 ppm Equiv. LHC 0-10,000 ppm Equiv. CO 0-10%, CO ₂ 0-16% NO 0-4000 ppm	Sampling System tubing/ hardware/accessories must be made of Teflon, stainless steel or glass only	Approval of system design and parts list, procure- ment control, inspection of system by Q.C. prior to on-line operation	System leak/compon- ent failure/incor- rect sample flow or pressure/calibration overdue	Correct variance and repeat test	Trained for operation of analytical system.
7. Instrument Calibration	Calibration gases with concentrations varying across the instrument range are used to identify the instrument curve for data reduction	05.775-15 TP-203 TP-758	Calibrated once every 30 days, Flowrate HHC, LHC, NO 10CFH, CO, CO, 5 CFH Concentration of gas should be known within 12% of true value	Weekly checks, calibration standards traceable to NBS/known to ±1% of true value or better. Curve generated must be within ±2% of all points.	Curve defined mathematically by least squares method. Curve approved by Data validation/ Audit.	Overdue calibration, system leak during calibration.	Locate and correct problem, recall-brate.	As above
8. CO ₂ /H ₂ O Response check	The Hydrocarbon instruments are checked monthly for interference from water wapor and carbon dioxide	35.775-15 TP-304	CU ₂ 100% - Response not to exceed 0.5% Sat. N ₂ 750F - LHC- 0.5% of full scale, HHC 0.5% of full scale.		Monthly check	Excessive inter- ference from CO ₂ /H ₂ O	Recharge filter cell with CO ₂ Replace de- tector.	As above
9. Sample Analysis	A portion of the exhaust gases are analyzed continuously from the first idle thru four nine-mode cycles ending with the engine at idle.	35.775-16, 17 TP-758	Chart Speed 6 in./min. Min. 4-nine mode cycles, 2 Idle modes-before and after test	Visually Monitor inst. inlet pressure during sampling ±1 in. H ₂ 0 Tol.	Data validation, calibration check, Q.C. audit	Excessive hangup Instrument drift in excess of 2% or other mal- function	Clean sampling system, repair instrument, repeat test	As above. Corrective action may require basic knowledge of electronic instruments.
10. Data Reduction	Direct computer analysis of instruments' output is used to reduce the data to brake specific emissions (gms/hr.)	85.775-16 TP-758	Chart reading should be within 0.5% of full scale. Chart speed 3 in./min. with marker to indicate computed segments.		Data validation, Computer program verification, random audit of test data.	Incorrect cycle seg- ments used for com- puter analysis, recorder mal- function.	Manually reduce data/repeat test	

FDA	TEST	PROCEDURE	Number	0	
		- KOCEDOKE	TP-750-G	Page	_ 07 _6
SUBJECT					
RECEIPT,	BUILD-UP	AND INSTALLATION OF	THE HEAVY-DUTY GASOLINE	TEST ENGI	1E
Referenc MSAPC ADV	e ISORY CI	RCULAR NO. 22A 4/3/7	73	Data Form	No.
Responsi HEAVY-DUT	ble Orga Y TEST O	Computer NONE	Program		
Test Witness HD - TEST SUPERVISOR					ce Interval
• • •	Test Rep	ort		Supersede NEW	S
CHECK LIS Report D CERTIFICA	istribut	ion EST OPERATIONS - DAT	PA FILE	Supersede	d by
	COMMENTS				
אבויואאאט/	COMMENT	•			
			•		
·					
İ					
ļ					
		ORIGINAL	RELEASE APPROVALS		
Office		Section	Signature		Date
Lab. Oper	<u> </u>	Quality Assurance	3.g/id/di-C	•	
Test Open		Chief			
HD Testin		Supervisor			
Certifica		Heavy Duty			
			REVISIONS	··	
Change Letter		Description of Chan	ige Appi	roval	Date
	1				
				•	

REVISIONS:	RECEIPT, BUILD-UP AND INSTALLATION
	OF HEAVY-DUTY GASOLINE TEST ENGINES

PROCEDURE NO. TP-750-G

PAGE_2_OF 6_

TEST PROCEDURE

1.0 PURPOSE

Outlines the proper procedure for receiving inspection and proper installation of engines received for emission testing.

2.0 TEST ARTICLE DESCRIPTION

Heavy-duty gasoline engines are shipped to the EPA for certification or other emission tests. These engines are prepared for testing by the Manufacturer according to the prescribed procedure in MSAPC Advisory Circular No. 22A.

3.0 REFERENCES

- 3.1 MSAPC Advisory Circular No. 22A dated April 3, 1973.
- 3.2 Federal Register, paragraphs 85.744-12 and 85.974-12.

4.0 REQUIRED EQUIPMENT/CONDITIONS

4.1 Small tools and necessary plumbing, thermocouple connectors etc., necessary for installation. See Section 8.0 for more detail.

5.0 PRECAUTIONS

- 5.1 Care should be taken when unloading the engine to place the forks or other lifting device properly to prevent damage to engine or components.
- 5.2 Engine should not be lifted nor moved by any part of the engine except by those means provided by the manufacturer, such as bed plate pallet, engine mounts, etc.
- 5.3 Never start the engine without first checking all installation connections and alignment.

6.0 VISUAL INSPECTION

- 6.1 Receiving Check engine for proper packaging and unloading requirements. After unloading, check for proper shipping documents and markings. Check for any signs of damage to shipping container and engine.
- 6.2 <u>Build-up</u> Check engine for specified temperature, cooling, fuel, drive shaft, and pressure connections.
- 6.3 <u>Installation</u> Check for proper coolant and oil level, distance from centerline of shaft to bed plate, engine lag down bolts.

7.0 TEST ARTICLE DESCRIPTION

See Sections 6.0 and 8.0 for preparation procedures.

REVISIONS:

RECEIPT, BUILD-UP AND INSTALLATION
OF HEAVY-DUTY GASOLINE TEST ENGINES

PROCEDURE NO.

TP-750-G

PAGE_3_OF6___

TEST PROCEDURE

8.	0	TEST	PROCEDURE

Test Sequence	Description	Data Output
101	Unload from truck using fork lift. Verify shipping weight does not exceed forklift capacity.	Check Sheet HD-750G-01
102	Fill out HD-receipt form. Explain all deficiencies. List all parts, number of shipping containers, shipping markings, other identifying marks and pertinent information.	Receiving Inspection Form No. HD-750G-02
103	Build-up and Install.	Check Sheet HD-750G-01
	o Thermocouple (s) o Water Hose (s) o Drive Shaft Check adapter plate bolts o Oil Pressure Line o Fuel Feed Line and Return Line o Fuel Pressure Line o Manifold Pressure Line	:
104	Check oil level (fill if required), distance from centerline of shaft to bed plate, engine lag down bolts.	Check Sheet HD-750G-01
105	Move engine to test cell and install on the test bed using the following sequence.	Check Sheet HD-750G-01
	 o Prepare engine test bed to receive engine and pre-aligned stand o Lift engine onto bed with hoist and bolt it in place o Bolt coupling to dynamometer and engine shaft; connect fuel oil and coolant systems using hand tools (refer to appropriate manufacturer's requirements for specifications) o Check carburetor inlet air filter o Connect thermocouples pressure gauges, vacualines, ignition, accelerator activator o Check engine for completeness, engine mounting, and engine alignment, o Position engine cooling fan if required 	um

REVISIONS: PROCEDURE NO. RECEIPT, BUILD-UP AND INSTALLATION OF HEAVY-DUTY GASOLINE TEST ENGINES TP-750-G **PROCEDURE** PAGE4_OF6_ TEST 8.0 TEST PROCEDURE (CONTINUED) Test Sequence Description Data Output o Install exhaust system, making 105 (cont'd) provisions for probe location o Verify compliance maintenance procedures. Engine - Dynamometer check out. After careful 106 inspection of the installation, the engine is run to make adjustments. o Using test cell dynamometer check list Check List confirm that all the necessary connections HD-750G-03 have been made, instruments and equipment properly installed, and all controls are properly set prior to engine start up o Check safety interlock system for proper installation o Check throttle positioning o Check oil and water for proper level o Check operation of system safety interlocks o Start engine and perform visual, audio, and functional inspection Listen for internal noises, such as piston slap, knocks, taps and gear noises that indicate irregularities in engine operation Check for fuel and lubricant leaks, check for exhaust and crankcase emission leaks o Bring engine to rated load and speed in gradual o Determine when engine conditions have stabilized and record BHP and fuel rate Dyno Log o Lug engine to peak torque speed and record torque and fuel rate o Check engine performance for compliance with manufacturer's specifications; if noncompliance is noted, contact supervisor o Shut down engine and dynamometer systems and record time and ambient temperature o Fill out request for repairs if necessary o All pretest functions should be completed with

107

Preparation of test engine for return to Manufacturer

a minimum amount of engine running time

Check List HD-750G-04

o Disconnect:

o Drive Shaft - Dyno End, only

REVISIONS:	RECEIPT, BUILD-UP AND INSTALLATION OF HEAVY-DUTY GASOLINE TEST ENGINES	PROCEDURE NO. TP-750-G
	TEST PROCEDURE	PAGE_5_OF 6
8.0 TEST PROCEDURE	(COMMITMED)	
O.O IESI PROCEDURE	(CONTINUED)	
Test Sequence	Description	Data Output
	o Engine Stand Lag Down Bolts o Accessory Stands o Exhaust System at exhaust manifold only o All temperature thermocouple wires from Control Room assembly o All sample probe lines from engine only o All fuel, oil, vacuum, manifold, pressu and feed lines from Control Room assemble only o Oil coolant hoses from Coolant package o Move Engine and Exhaust System o Gasoline Engine (s) to Room 409	n 7 ure
0	Remove and put in proper place O All thermocouples, wires and fitting (if installed by E.P.A.) O Water Hoses O Drive Shaft O All fuel, oil, vacuum, manifold, pressure and feed lines and fittings Drain O Follow manufacturer's recommended procedure for draining coolant Drain oil if necessary	e
o	Re-Install o Exhaust System and all other engine parts and accessories received	

108

NOTE:

Check HD Receiving form to assure shipment is complete as received

Complete Shipping Order No. HD-750G-05

TECT DOCEDURE DACES DES	REVISIONS:	•	D-UP AND INSTALLATION GASOLINE TEST ENGINES	PROCEDURE NO.
TEST PROCEDURE PAGES OF S		TEST	PROCEDURE	PAGE OF

9.0 DATA INPUT

9.1 Check sheets validated by supervisor and place into test file.

10.0 DATA ANALYSIS

None

11.0 DATA OUTPUT

None

12.0 ACCEPTANCE CRITERIA

- 12.1 Engine as received must conform to specifications outlined in MSAPC Advisory Circular No. 22A (4-3-73).
- 12.2 Engine must conform to manufacturer's specifications.
- 12.3 Engine must not exhibit any malfunctions such as oil leaks, engine noise, erratic running or overheating.

13.0 QUALITY PROVISIONS

- 13.1 Engine returned to manufacturer if all specifications not met.
- 13.2 Engine installation approved by supervisor and certification engineer.
- 13.3 Data validation inspects check lists for discrepancies and completeness.
- 13.4 Discrepancies noted during receiving inspection reported to supervisor and quality assurance.

Check List - Receipt, Build-Up And Installation Gasoline Test Engine

Description		Oper. Init.
Unload from truck		
Visual Inspection:	Fill out HD-receipt form Explain all deficiencies List all parts	
Build-up and Install:	Temperature Thermocouple (s) Water Hose (s) Drive Shaft (check adaptor plate bolts) Oil Pressure Line Fuel Feed Line Vacuum Line(s) Ignition Wiring Fuel Pressure Line	
Check:	Oil Level (fill if required) Distance C/L shaft to bed plate Engine Lag Down Bolts	
Move to test cell:	Center engine stand on bed plate and lag down	
Connect:	Temperature Thermocouple (s) Water Hoses Drive Shaft Oil Pressure Line Fuel Feed Line Fuel Pressure Line Vacuum Line(s) Ignition Line Accelerator Actuator Exhaust System Exhaust Sample Probes Cooling Fan (if required)	

Date	Manufacturer		
Engine C.I.D.	Engine I.D.#		
Test Type Cert.	Dura.	Correl.	Other
# Pieces			
Description			
Condition			
Received by			
Test Date	Took #		
EPA	lest #	- DD	
нс	Accel	<u>EPA</u>	
co		·	
NO _x			
Manufacturer's Rep. Signature			
Certification Rep. Signature			_
Returned Date			

Form HD-750G-02 - Receiving Inspection Report

Check List Test Cell 3 and 4 Gasoline Engine Dynamometer Operation

Water ON Expansion Tank - 2/3 to 3/4 full Booster Pump ON Air Pressure - ON Control Boom Assembly: Vacuum Line - Installed Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected Throttle Control - Connected
Booster Pump ON Air Pressure - ON Control Boom Assembly: Vacuum Line - Installed Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Control Boom Assembly: Vacuum Line - Installed Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Control Boom Assembly: Vacuum Line - Installed Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Control Boom Assembly: Vacuum Line - Installed Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Vacuum Line - Installed Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Fuel Line - Installed Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Fuel Pressure Line - Installed Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Oil Pressure Line - Installed Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Temperature Thermocouple (s) - Installed Ignition Wire - Connected
Ignition Wire - Connected
Ignition Wire - Connected
Dynamometers:
Drive Shaft - Connected
Drive Shaft Guard - Connected
Engine
Water Hoses - Connected
Exhaust Muffler etc: - Connected
Exhaust Sample Probes - Connected
Fuel Regulator - Correct Setting
Cooler Fan (if used) - ON
Console
All Potentiometers in OFF position Power ON in M.G. Room
M. G. set - ON- 10 min. warm-up min. Primary Power - ON
Vacuum Manometer at zero Ignition - ON
Rotation - CW - front side Temp. Recorder - ON
CCW - rear side
Inertia - Pos. position Wet Bulb thermo-filled
Mode - Manual and power ON
Strip chart recorder - ON

Check List - Preparation of Test Engine for Return to Mfr.

Description		Oper. Init.
Disconnect:	Drive Shaft - Dyno End, only. Engine Stand Lag Down Bolts. Accessory Stands. Water Hoses from Coolant package. Exhaust System at Exhaust manifold only. All Temp. thermocouple wires from Control Boom Assembly. All sample probe lines from engine only. All fuel, oil, vacuum, manifold, pressure, and feed lines from Control Boom Assembly only. Oil coolant hoses from Coolant package.	
Move Engine an	d Exhaust System Heavy-Duty Gasoline Engine(s) to Room 409.	
Disconnect,	Remove and put in proper place: All Thermocouples, wires and fittings (if installed by E.P.A.) Water Hoses Drive Shaft All fuel, oil, vacuum, manifold, pressure and feed lines and fittings.	
Drain:	Coolant complete; oil (if required).	
Re-Install:	All pipe plugs, cap plugs and other fittings removed by E.P.A.	
Disassemble: Pack in Box: Strap to Skid:	Exhaust System and all other engine parts and accessories received.	

Note: Check HD Rec. form to assure shipment is

complete as received.

Environmental Protection Agency Office of Air & Water Programs 2565 Plymouth Road Ann Arbor, Michigan 48105

SHIPPING ORDER

		No.	
		Date	
Ship To :		Charge To:	
Address :		Address :	
Attention:		Attention:	
	is herewith returned per	/engine(s) now on consigment/loa signature of your carrier (or, o	
Quantity	Description	Ser. 1	No.
·			
The above item	s were received by	(Signature)	
on(D	ate)		

14

EPA	TEST	PROCEDURE	TP-757	Page 1	of <u>6</u>
SUBJECT					
HEAVY-DUTY GASOLINE ENGINE DYNAMOMETER TEST CYCLE					
Reference FEDERAL		ER VOL. 40 NO. 40 FEBI	RUARY 27, 1975	Data Form	No.
Responsi		anization		Computer I	Program
Test Wit		EAVY-DUTY TESTING		Performand EACH TEST	ce Interval
Type of	Test Re	port		Supersede	5
	R OUTPU			NEW	
	Distribu B. CHIEF	tion /MFR. REP./DATA FILE		Superseded	d by
REMARKS/	COMMENT	S			
1					
İ					
}					
l					
		ORIGINAL R	ELEASE APPROVALS		
Office		Section	Signatur	e	Date
PROGRAM M	1GMT	QUALITY ASSURANCE		·	
LAB. BRAN		CHIEF			
LAB, BRAN	ICH	TEST OPERATIONS CHI	EF		
		D	EVISIONS		
			F11210112		
Change Letter		Description of Chang	e	Approval	Date
	1				
	1				
,					
,	1				
	1				

REVISIONS:	HEAVY-DUTY GASOLINE ENGINE DYNAMOMETER TEST CYCLE	PROCEDURE NO.
	TEST PROCEDURE	PAGE_2_OF 6

1.0 PURPOSE

A prescribed sequence of engine operating conditions are conducted on an engine dynamometer to determine conformity with the standards stated in the Federal Register.

2.0 TEST ARTICLE DESCRIPTION

Applicable to new gasoline heavy-duty engines beginning with the 1974 model year. A heavy-duty engine is defined as any engine which the engine manufacturer could reasonably expect to be used for motive power in a heavy-duty vehicle.

3.0 REFERENCES

3.1 Federal Register, Volume 40, Number 40, February 27, 1975. pp 8482 - 8495

4.0 REQUIRED EQUIPMENT/CONDITIONS

- 4.1 An engine dynamometer capable of maintaining constant speed <u>+</u> 100 RPM from full throttle to closed throttle motoring.
- 4.2 A chassis-type exhaust system or equivalent.
- 4.3 A radiator typical of that used with the engine in a vehicle or equivalent.
- 4.4 Auxiliary fixed speed cooling fan (if required.)
- 4.5 Tape recorder with prerecorded instructions for dynamometer operator.
- 4.6 Fuel shall be Indolene clear or Indolene HO if catalyst equipped.

5.0 PRECAUTIONS

- 5.1 Maintain ambient temperature of test cell between 60°F to 68°F during engine soak period and between 68°F to 86°F during test cycle.
- 5.2 Tolerances for time, speed and manifold vacuum must be followed during cycle in order to perform valid test.
- 5.3 Visual and audible observation of engine-dyno operation should be performed during test. Shut down engine-dyno if abnormalities are detected.

6.1 Perform v		PROCED	IDE	Ţ		
			OKL		PAGE3	OF <u>6</u>
6.1 Perform v	ION					
	isual inspection	of engine-dyn	o systems	prior to	o start u	p.
6.2 Inspect for	uel system for le	aks before an	d after to	est.		
.0 TEST ARTICLE P	REPARATION					
Refer to TP-75	0-G.					
•						
		·				
		•				

REVISIONS:

HEAVY-DUTY GASOLINE ENGINE DYNAMOMETER TEST CYCLE

PROCEDURE NO.

TP-757

PAGE 4 OF 6

TEST PROCEDURE

8.0 TEST PROCEDURE

An initial 5-minute idle, two warm-up cycles and two hot cycles constitute a complete dynamometer run. Idle modes may be run at the beginning and end of each test only, thus eliminating the need to change speed between cycles.

Test Sequence	Test Description	Data Output
100	PRECONDITIONING	
101	Start cooling system.	
102	Start the engine and precondition it by operation over one or more cycles prescribed for service accumulation or dynamometer operation until the engine has reached normal operating conditions.	Dyno Log Book Water Temp. ^O F
103	Shut down engine and cooling system and allow to stand for at least 1 hour but not more than 2 hours.	Record Soak Time
200	TEST CYCLE	
201	Start cooling system.	
202	Start engine and operate within the manufacturer's RPM specifications for off-idle operation for 5 minutes.	
203	Return the engine throttle control to the normal idle position.	
204	Turn on prerecorded tape and run four nine mode cycles according to the following time, speed, load requirements.	Continuous Record Of RPM, Manifold Vacuum vs. Time

REVISIONS:	HEAVY-DU
	DYNAMO

HEAVY-DUTY GASOLINE ENGINE DYNAMOMETER TEST CYCLE

PROCEDURE NO.

TP-757

PAGE_5 OF 6_

TEST PROCEDURE

Test Sequence

Test Description

Data Output

The /Ux

SEQUENCE NO. MODE	MANIFOLD VACUUM	TIME IN MODE-SECS.	CUMULATIVE TIME-SECS.	WEIGHTING FACTORS
1Idle		70	70	0.232
2Cruise	16" Hg	23	93	.077
3PTA	10" Hg	44	137	.147
4Cruise	16" Hg	23	160	.077
5PTD	19" Hg	17	177	.057
6Cruise	16" Hg	23	200	.077
7FL	3" Hg	34	234	.113
8Cruise	16" Hg	23	257	.077
9CT		43	300	.143

- o The engine dynamometer shall be operated at a constant speed of 2,000 r.p.m. +100 r.p.m. (Speed deviations, not to exceed 200 r.p.m., will be allowed during the first four seconds of each mode.)
- o The idle operating mode shall be carried out at the manufacturer's recommended engine speed. The CT operating mode shall be carried out at the same engine speed as above.
- o If the specified manifold vacuum can not be reached during the PTD mode, the engine shall be operated at closed throttle during that mode. If the specified manifold vacuum can not be reached during the FL mode, the engine shall be operated at wide open throttle during that mode.

205	mode.	Torque
206	Shut down engine and cooling system after last idle period.	Record Engine Running Time

	TEST PROCEDURE	P
	DYNAMOMETER TEST CYCLE	١.
REVISIONS:	HEAVY-DUTY GASOLINE ENGINE	P

PROCEDURE NO.

PAGE_6_OF6__

9.0 DATA INPUT

- 9.1 Test number/system tested/inst. oper./dyno oper./engine make/I.D. #/mfr. data.
- 9.2 Engine date of manufacture/engine hours/CID/family/idle RPM/carb/BBl.
- 9.3 Date and time of day for each part of the test schedule.
- 9.4 Intake manifold vacuum and engine RPM continuously recorded on the same chart.

10.0 DATA ANALYSIS

10.1 Determine whether the cycle was run in accordance with Acceptance Criteria (12.0) by observing chart peaks, speed trace and manifold vacuum traces.

11.0 DATA OUTPUT

11.1 All data entries and chart records maintained in HD Test File.

12.0 ACCEPTANCE CRITERIA

- 12.1 The test will be invalidated if there is a deviation by more than:
 - (a) two seconds from the specified time for the CT mode, or
 - (b) 0.3 inch Hg during the cruise and PTD modes, or more than 0.2 inch Hg during the PTA and FL modes from the specified mode vacuums during the last ten seconds of a mode, or
 - (c) 200 r.p.m. during the first four seconds of each mode, or 100 r.p.m. during the remainder of each mode.

13.0 QUALITY PROVISIONS

- 13.1 Dynamometer calibrated monthly according to TP-250. Weekly single point torque check.
- 13.2 Fuel flow meter calibrated using dead weight tester.
- 13.3 RPM/torque recorder output checked prior to each test. Recorder serviced and calibrated at 3 month intervals.
- 13.4 Driving tape checked monthly for proper timing and wear.

EPA	TEST	PROCEDURE	TP-758	Page 1	_ of7
SUBJECT					
HEAVY-DUTY GASOLINE ENGINE EXHAUST ANALYSIS PROCEDURE, CO, CO, HC AND NO					
Referenc FEDERAL	e REGISTE	ER VOL. 40 NO. 40 FEB	RUARY 27, 1975	Data Form	No.
		anization		Computer 1	Program
TEST OP	ERATIONS	5		SAQP: GAS	
Test Wit	ness			Performan	ce Interval
		EAVY-DUTY TESTING	· • • • • • • • • • • • • • • • • • • •	EACH TEST	
Type of				Supersede	5
COMPUTE				NEW	F
Report D CSD/LAB	. CHIEF	/MFR. REP./DATA FILE		Supersede	ı Dy
REMARKS/	COMMENTS	S			
<u> </u>					
					-
·					
		ORTGINAL	RELEASE APPROVALS		
		T			
Office Office		Section	Signature		Date
PROGRAM M		OUALITY ASSURANCE		•	
LAB. BRAN		CHIEF TEST OPERATIONS CHIE	EF	,	
11111			·	-	
			REVISIONS		
Change				_	
Letter		Description of Chan	ge App	roval	Date
					* ·
					:
					. M
				1.2	
				e	er en en
			Ì		

HEAVY-DUTY GASOLINE ENGINE EXHAUST	PROCEDURE NO.
 ANALYSIS PROCEDURE, CO, CO2, HC AND NO.	TP-758
TEST PROCEDURE	PAGE_2_OF 7

1.0 PURPOSE

Exhaust gases are analyzed continuously during a prescribed sequence of engine operating conditions to determine conformity with the standards specified in the Federal Register.

2.0 TEST ARTICLE DESCRIPTION

Applicable to new heavy-duty engines beginning with the 1974 model year. A heavy-duty engine is defined as any engine which the engine manufacturer could reasonably expect to be used for motive power in a heavy-duty vehicle.

3.0 REFERENCES

3.1 Federal Register, Volume 40 Number 40 February 27, 1975. pp 8482-8495

4.0 REQUIRED EQUIPMENT/CONDITIONS

- 4.1 Exhaust gas sampling and analytical system conforming to schematic H774-1 (Attachment No. 1) with the following instruments:
 - A. Nitric oxide NDIR analyzer, range 0-4000 PPM
 - B. Carbon monoxide NDIR analyzer, range 0-10 percent
 - C. Carbon dioxide NDIR analyzer, range 0-16 percent
 - D. High-range hydrocarbon NDIR analyzer, range 0-10,000 PPM hexane equivalent (propane conc. x 0.52)
 - E. Low-range hydrocarbon NDIR analyzer, range 0-1,000 PPM hexane equivalent.

Sample lines, filter, valves, pumps, flowmeters and other components which are in contact with exhaust sample must be of stainless steel, teflon, viton or glass construction.

4.2 Zero grade air or nitrogen meeting the following maximum requirements of contamination level

Carbon Response = 10 ppm CO Response = 10 ppm NO Response = 1 ppm CO₂ Response = 400 ppm

REVISIONS:

HEAVY-DUTY GASOLINE ENGINE EXHAUST ANALYSIS PROCEDURE, CO, CO, HC AND NO, PROCEDURE NO.

PAGE 3 OF 7

TEST PROCEDURE

4.3 Calibration gases with concentrations known to be within ± 2 percent of true value as follows (N₂ diluent):

			co and co_2
Low range	High range	NO ana-	analyzers-Blend
HC analyz-	HC analyz-	lyzer-	of CO and CO ₂
er-Hexane	er-Hexane	NO	containing
equivalent ^l	equivalent		
			CO plus CO ₂

			Mole	Mole
p.p.m	p.p.m	p.p.m	percent	percent
100	600	250	0.5	16.0
200	1,000	500	1.0	15.0
300	1,500	750	2.0	14.0
400	2,500	1,000	3.0	13.0
600	4,000	1,500	4.0	12.0
800	6,000	2,000	6.0	10.0
1,000	8,000	2,500	8.0	8.0
	10,000	3,000	10.0	6.0
		3,500	• • • • • • • •	
		4,000	• • • • • • •	• • • • • •

The hexane equivalent of propane when used as the normalizing gas for calibrating nondispersive infrared analyzer is prescribed to be 0.52 (propane concentration x 0.52 = hexane equivalent concentration). Minimum storage temperature of the cylinders shall be 60°F; minimum use temperature shall be 68°F.

NOTE: Concentration values should be traceable to EPA gravimetric standards.

- 4.4 Daily working gases (span gases) equivalent to 80 to 100 percent full scale response for each range.
- 4.5 Recorders (4 channels) for continuous record of analyzer output and calibration.

5.0 PRECAUTIONS

- 5.1 Safety precautions should be followed when handling compressed gases.

 NO and CO are toxic gases.
- 5.2 Insure gas cylingers have adequate pressure for testing \$\mathcal{p}\$200 psig.)
- 5.3 When calibrating/spanning/sampling the identical instrument inlet pressure must be used. Adjust flows to pressure reading rather than flowmeter.

REVISIONS:	HEAVY-DUTY GASOLINE ENGINE EXHAUST ANALYSIS PROCEDURE, CO, CO ₂ , HC AND NO _X	PROCEDURE NO. TP-758
·	TEST PROCEDURE	PAGE4_OF 7

- 5.4 Insure that flowrates are adequate to minimize response time.
- 5.5 Check the condition of the drier in the nitric oxide analyzer sampling line. Replace the drying agent if necessary.
- 5.6 Insure that the sample probe(s) is properly inserted 2 feet into tailpipe.

6.0 VISUAL INSPECTION

- 6.1 Inspect recorder connections and other electrical connections to insure they are secure.
- 6.2 Inspect pressure gauges and flowmeters for proper operation, stuck floats, pointers, etc.
- 6.3 Inspect system vent for proper connection.

7.0 TEST ARTICLE PREPARATION

- 7.1 Leak check exhaust gas sampling system by closing off valve at sample probe. All pressure gauges should drop to zero reading.
- 7.2 Calibrate exhaust emission analyzer system using zero and span gases. Adjust instrument gain and zero as required. Analyzers require a minimum of 2 hours warm-up, therefore they are usually never turned off, except for chopper motors, while they are in service.
- 7.3 The following inter-service checks are performed monthly.
 - (5) Check response of hydrocarbon analyzer to 100 percent CO. If response is greater than 0.5 percent full scale, refill filter cells with 100 percent CO, and recheck. Note any remaining response on chart. If response still exceeds 0.5 percent, replace detector.
 - (6) Check response of hydrocarbon analyzers to nitrogen saturated with water at ambient temperature. Record ambient temperature. If the low-range instrument response exceeds 5 percent of full scale with saturated nitrogen at 75°F., replace the detector. If the high-range response exceeds 0.5 percent of full scale, check detector on low-range instrument, then reject if response exceed 5 percent of full scale at 75°F.
- 7.4 Change filter papers and back flush water traps and sample line.
- 7.5 Turn-on sample pumps.

REVISIONS:

HEAVY-DUTY GASOLINE ENGINE EXHAUST ANALYSIS PROCEDURE, CO, CO2, HC AND NOX

PROCEDURE NO.

TP-758

PAGE_5_OF_7_

TEST PROCEDURE

8.0 TEST PROCEDURE

The exhaust sample is analyzed continuously during 4 nine-mode cycles.

Test Sequence	Test Description	Data Output
101	Check zero, span, flow and pressure immediately prior to start of cycle.	Recorder Defl.
102	Start sample flow and recorders when engine throttle control is returned to normal idle position from the initial off-idle position. Chart speed should be 6 inch per minute.	Recorder Defl.
103	Sample and analyze exhaust gases for 4 nine-mode cycles (TP-757) including the final idle mode.	Continuous Trace, Computer Input
104	Purge sample line with nitrogen to establish a a constant hydrocarbon "hangup".	HC Defl. Vs. Time
105	Recheck zero, span, flowmeter, pressure gauge readings.	

REVISIONS:	HEAVY-DUTY GASOLINE	ENGINE EXHAUST
	ANALYSIS PROCEDURE,	CO, CO ₂ , HC AND NO _X

PROCEDURE NO.

TP-758

PAGE_6_OF 7_

9.0 DATA INPUT

9.1 The following steps are performed by direct computer analysis.

(a) Time correlate the hydrocarbon, carbon monoxide, carbon dioxide, and nitric oxide charts. Determine the location on the chart of analyzer response corresponding to each mode. Determine and compensate for trace abnormalities.

TEST PROCEDURE

- (b) Locate the last 3 seconds of the HC, CO, CO₂, and NO traces obtained from the 3 inch, 10 inch, 16 inch, 19 inch and idle modes. Divide this portion of each trace into a minimum of three segments of equal length. Determine the chart reading at the end of each segment to within 0.5 percent of full scale. Convert these readings into concentration values. Determine the average of these values.
- (c) The values recorded for the initial idle mode are used for both warm-up cycles 1 and 2. The final idle mode values are applied to hot cycles 3 and 4.
- (d) Locate the HC, CO, CO₂, and NO closed throttle mode traces. Divide each trace into a minimum of 43 segments of equal length. Determine the chart reading at the end of each segmentss within 0.5 percent of full scale. Convert these reading into concentration values. Determine the average of these values.
- 9.2 Fuel consumption in lbs. per hour are determined for each mode including idle.
- 9.3 Record test number, instrument operators, all pertinent instrument information such as tuning-gain-serial numbers-detector number-range, barometric pressure, intake air temperature and humidity.

10.0 DATA ANALYSIS

10.1 Analysis of all recorded data performed by Data Validation for completeness, accuracy and conformance to specified procedure.

11.0 DATA OUTPUT

11.1 Concentration values are reduced by computer to brake specific values (gms/hr) for CO, HC and NO_x using specified weighting and humidity correction factors.

REVISIONS:	HEAVY-DUTY GASOLINE ENGINE EXHAUST ANALYSIS PROCEDURE, CO, CO ₂ , HC AND NO _X	PROCEDURE NO. TP-758
	TEST PROCEDURE	PAGE_7_OF 7_

12.0 ACCEPTANCE CRITERIA

- 12.1 Upon completion of the test, the hydrocarbon concentration (hangup) shall drop to 5 percent or less of full scale within 10 seconds and 3 percent or less of full scale within 3 minutes, while being purged with nitrogen at the specified flow rate, or the test is invalid.
- 12.2 A drift in excess of 2 percent of full scale in the calibration of any one or the exhaust emission analyzers invalidates the test.

13.0 QUALITY PROVISIONS

- 13.1 Analyzer calibrations and interference checks performed monthly while in service.
- 13.2 Calibration checks performed before and after each test.
- 13.3 Quality Assurance performs audit of procedure and test cell equipment on non-routine basis.

FLOW SCHEMATIC OF EXHAUST GAS ANALYSIS SYSTEM EMPLOYED BY EPA

