

DRAFT

REVISED DRAFT FINAL REPORT

THEORETICAL EVALUATION OF SITES LOCATED IN THE ZONE OF SATURATION

Contract No. 68-01-6438
Task No. 012

Prepared for:

Mr. James Bland
Project Officer (5 AHWM)
U.S. Environmental Protection Agency
Region V
Chicago, Illinois 60604

Prepared by:

Versar Inc.
6850 Versar Center
P.O. Box 1549
Springfield, Virginia 22151

and

JRB Associates
8400 Westpark Drive
McLean, Virginia 22102

Date Prepared:

April 6, 1983

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	DRAIN THEORY	4
2.1	Drain Spacing and Head Levels	4
2.1.1	Drains On Impervious Barriers	5
2.1.2	Drains Above Impervious Barriers.	7
2.1.3	Drains On Sloping Impervious Barriers	11
2.2	Drain Pipe Sizing	13
2.2.1	Hydraulic Gradient (i) and Roughness Coefficient	14
2.2.2	Discharge (Q)	17
2.2.3	Pipe Size	21
2.3	Filters and Envelopes	23
2.3.1	Function of Filters and Envelopes	23
2.3.2	Design of Sand and Gravel Filters	24
2.3.3	Design of Sand and Gravel Envelopes	26
2.3.4	Synthetic Filters	26
3.0	DESIGN AND CONSTRUCTION	28
3.1	Hypothetical Site	28
3.2	Sensitivity Analysis	31
3.2.1	Drains On Impermeable Barriers	31
3.2.2	Drains On Sloping Impervious Barriers	34
3.2.3	Drains Above An Impervious Barrier	40
3.3	Application	40
3.3.1	Parameter Estimation	43
3.3.2	Landfill Size	44
3.3.3	Example Problem	44
3.4	Application	47
3.4.1	Construction Inspection	47
3.4.2	Drain System Maintenance.	48
3.4.3	Future Operating Conditions	49

TABLE OF CONTENTS
(Continued)

4.0	FLOW NET ANALYSIS	50
4.1	Introduction	50
4.2	Initial Conditions	52
4.3	Parameter Analysis	55
5.0	MODELS	60
5.1	Release Rate Models	60
5.1.1	Fundamentals	60
5.1.1.1	Leachate Generation	60
5.1.1.2	Leachate Constituent Concentrations. .	66
5.1.1.3	Leachate Release	66
5.1.2	Selected Release Rate Models	69
5.2	Solute Transport Models	77
5.2.1	Fundamentals	77
5.2.1.1	Analytical Models	80
5.2.1.2	Numerical Models	81
5.2.2	Selected Solute Transport Models	82
5.2.2.1	Analytical Models	86
5.2.2.2	Numerical Models	90
5.3	Model Limitations	94
6.0	RECOMMENDATIONS	95
7.0	BIBLIOGRAPHY	97

LIST OF TABLES

2-1	Values for the Equivalent Depth d of Hooghoudt	10
2-2	Minimum Hydraulic Gradients for Closed Pipes	15
2-3	Drain Grades for Selected Critical Velocities	16
3-1	Range of Site Variables	30
3-2	Drain Length Spacing (m) for Drains on an Impermeable Barrier	32
3-3	Values of h/L for Various $C=q/k_1$ and Angles α	36
3-4	Drain Spacing (m) for Head Maintenance Levels of 2 Meters	38
3-5	Drain Spacing (m) for Drains Above an Impermeable Barrier	41
3-6	Example Data Set	45
5-1	Major Factors Affecting Leachate Generation	62
5-2	Factors Affecting Leachate Constituent Concentrations .	67
5-3	Factors Affecting Leachate Release	68
5-4	Release Rate Models	70
5-5	Solute Transport Models	83

LIST OF FIGURES

1-1	Typical Stratigraphic Column of Zone of Saturation Sites in Wisconsin	2
2-1	Drains Resting on an Impervious Barrier	6
2-2	Flow to Drains Above an Impervious Barrier	8
2-3	Drains on Sloping Impermeable Barrier	12
2-4	Flow Components to a Landfill	18
2-5	Division of a Symmetrical Drawdown Drain Problem Into Two Equivalent Fragments.	20
2-6	Capacity Chart $n = 0.013$	22
3-1	Hypothetical Zone of Saturation Landfill.	29
3-2	Drain Length versus Flow Rates for Head Levels Equal to 1 Meter	33
3-3	Plot of h/L versus $h/I = \tan \alpha$ for Drain and Sloping Impervious Layers	37
3-4	Drain Length (L) versus $c - q/k_1$	39
3-5	Drain Spacing (L) versus Inflow rates (q)	42
4-1	Cross Section of Typical Zone of Saturation Landfill	51
4-2	Inflow With Typical Landfill Cell	54
4-3	Flow Nets With Different Leachate Levels	56
4-4	Flow Nets With Different Vertical Gradients	57
4-5	Flow Nets With Different Numbers of Drains.	58
5-1	Major Components of Groundwater Transport Equations	79


ACKNOWLEDGMENTS

This report was prepared by Dr. Edward Repa, Ms. Kathi Wagner, and Mr. Rodger Wetzel of JRB Associates, and Mr. Michael Christopher of Versar Inc., under the direction of Dr. G. Thomas Farmer, Task Manager. This report was prepared for the Wisconsin Department of Natural Resources under the U.S. EPA's Technical Assistance Project sponsored by U.S. EPA, Region V.

1.0 INTRODUCTION

The State of Wisconsin and much of EPA Region V are located in a portion of the United States characterized by thick surficial deposits of saturated glacial till underlain by fractured sedimentary or crystalline rock. A typical stratigraphic column for Wisconsin is shown in Figure 1-1. Landfill site design in this part of the country is complicated by the hydrology of the zone of saturation. At these sites, the glacial clay deposits into which the landfills are built act as limited unconfined aquifers. Hydraulic conductivities of the clays range from 10^{-5} cm/sec, where the clays are fractured, to 10^{-7} cm/sec, where the clays are unfractured (Newport, 1962). Underlying the clays are thick units of dolomite and sandstone which act as confined aquifers. Confining pressures in these units can bring groundwater to the land surface in drilled wells. Recharge of these underlying units occurs at or near outcrops.

Siting landfills in this region, especially those which will accept hazardous wastes, is a problem because the base grade of the facility is typically below the water table (i.e., in the zone of saturation). As a result of having the base grade below the groundwater table, the potential for accelerated leachate generation and contaminate release is greatly enhanced. To alleviate this problem, landfill operators are required to manage groundwater and leachate in the landfills so that inward hydraulic gradients are constantly maintained, thereby limiting the possibility of contaminant escape. The method utilized to maintain inward hydraulic gradients is a drainage collection system installed on the base of the landfill. The drainage system allows for the maintenance of landfill head levels which are lower than the natural groundwater table (i.e., inward hydraulic gradients).



Vertical Scale 1"=200'

Figure 1-1. Typical Stratigraphic Column of Zone of Saturation
Sites in Wisconsin (City of Fond du Lac) (Newport, 1962)

The purpose of this study was to perform a theoretical evaluation of the validity of the presently used landfill management schemes for groundwater and leachate at sites located in the zone of saturation. This evaluation included flow net and parameter sensitivity analyses. The key parameters that were evaluated include:

- o Drain spacing.
- o Hydraulic conductivities of the landfill and natural soils surrounding the site.
- o Inflow rates resulting from groundwater infringement and leachate generation.
- o Head maintenance levels within the landfill.
- o Pipe sizing.
- o Drainage blanket use.

Other parameters addressed include landfill dimensions, construction inspections, and future operating conditions. Drainage theory and selected models for predicting release rates and solute transport are also described.

The results of this study should assist permit writers in determining engineering design modifications and site monitoring requirements, as well as aid in establishing a basis for future design protocols for zone of saturation landfills.

2.0 DRAIN THEORY

There are three major elements to consider in the design of a subsurface drainage system suitable for zone of saturation landfills:

- o The drain spacing required to achieve the desired head maintenance levels.
- o The hydraulic design of the conduit, including the pipe diameter and gradient.
- o The properties of the drain filter and envelope.

This section briefly describes the principles involved in determining a desirable drain slope and spacing, and in selecting appropriate drain materials.

2.1 Drain Spacing and Head Levels

There are numerous analytical solutions and models that have been developed for estimating the drain spacing required to maintain head levels at a predetermined height in saturated media. This section presents the analytical solutions for determining drain spacing based on maintenance head levels, permeabilities, and flow rates for:

- o Drains resting on an impermeable barrier
- o Drains installed above an impermeable barrier
- o Drains resting on an impermeable barrier that slopes symmetrically at an angle to the drains.

The equations presented here assume that steady state conditions exist, that recharge distribution and leachate generation over the area between the drains is uniform, and that the soil is homogeneous. Most real world situations do not fully meet these criteria; therefore, the results obtained should be considered approximate. In using the equations for designing a landfill drain system, a conservative approach

should be taken to ensure that head maintenance levels are at or below the desired height.

2.1.1 Drains on Impervious Barriers

Groundwater flow to drains resting on a horizontal (flat) impervious barrier can be represented (Van Schlifgaarde, 1974; Wesseling, 1973) by the equation:

$$L = [(8KDh + 4Kh^2)/q]^{0.5}$$

where:

L = drain spacing (m)

K = hydraulic conductivity of the drained material (m/day)

D = distance between the water level in the drain line and the impermeable barrier (m)

h = water table height above the drain levels at the midpoint between two drains (m)

q = leachate generation rate (m/day) [equal to total inflow (m³/day) divided by landfill area (m²)]

Figure 2-1 illustrates the relationship between these terms. When two parallel drain lines are installed properly, each line causes the establishment of a drawdown curve that, in theory, will intersect midway between the two drain lines. In solutions to gravity flow problems, the distance from the drain to a point where the drawdown can be considered insignificant ($\Delta h = 0$) is equal to half of the drain spacing (L/2). This distance, L, is commonly referred to as the "zone of influence" of the drain.

For a pipe drain resting on an impermeable barrier, the parameter D approximately equals the radius of the pipe and hence can be very small in comparison to h (the water table height above the drain). Then, since the term 8KDh becomes very small (≈ 0), equation 1 can be simplified to:

$$L = [(4Kh^2)/q]^{0.5}$$

Equation 2 represents horizontal flow to the drains above the drain level.




Figure 2-1: Drains Resting On An Impervious Barrier

Drain spacing (L) and hydraulic head level (h) in the equations are interdependent design variables which are a function of the leachate generation rate (q) and hydraulic conductivity (K) of the drained material. Assuming a constant leachate generation rate and hydraulic conductivity, the closer two drains are spaced the more their drawdown curves will overlap and the lower the hydraulic head levels between the drains will be. Therefore, in order to space the drains at the required distance to achieve the desired head maintenance levels, the hydraulic conductivity of the landfill material and the quantity of leachate generated must be determined to a reasonable degree of accuracy.

2.1.2 Drains Above Impervious Barriers

Equations 1 and 2 are suitable for estimating drain spacing and head levels if the drains are located on an impervious barrier, as is the case with most landfill operations. In using drainage system design equations, a layer is generally considered impervious if it has a permeability at least 10 times less than the overlaying layer (i.e., $K_{\text{above}}/K_{\text{below}} > 10$). The clay base of a landfill may not act as an impermeable layer in the design equations if:

- o Clays are not adequately compacted to produce the desired permeability
- o Clays are fractured (naturally or during placement)
- o Clays are not uniform (e.g., contain sandy zones)
- o Landfill material has a permeability comparable to the clay liner.

Where drains are not installed on impermeable barriers, flow to the drains is radial (as illustrated in Figure 2-2). In this case the drains are considered to be installed at the interface of a two-layered soil with hydraulic conductivities of K_1 and K_2 (as shown in Figure 2-2). Substituting the hydraulic conductivity of the material below the drain (K_2) into the first term of the right hand side of equation 1 compensates for radial flow to the drain system, and gives:

$$L = [(8K_2Dh = 4K_1h^2)/q]^{0.5} \quad (3)$$




Figure 2-2: Radial Flow to Drains Above An Impervious Barrier

However, the drain spacing calculated by equation 3 does not take into account the fact that flow velocity in the vicinity of the drain is higher than elsewhere in the flow region. If the flow velocity was uniform, the reduction in hydraulic head caused by the drain would be distributed evenly around the drain. But, because of the non-uniform velocity, a proportionally higher loss of head occurs close to the drain, and the actual water table elevation (h) will stand higher than expected with drains spaced according to equation 3.

To account for the increase in h caused by radial flow, Hooghoudt (1940) introduced a reduction of the parameter D to a smaller equivalent depth, d. The equation that was developed to take into account radial flow can be rewritten as:

$$L = [(8K_2dh + 4K_1h^2)/q]^{0.5} \quad (4)$$

where the new term d is the equivalent depth (m)

Equation 4 shows the drain spacing L is dependent on the equivalent depth d. But the value of d is calculated from a specified value for L, so equation 4 cannot be solved explicitly in terms of L. The use of this equation as a drain spacing formula involves either a trial and error procedure of selecting d and L until both sides of the equation are equal or the use of nomographs which have been developed specifically for equivalent depth and drain spacing. Table 2-1 gives values of the equivalent depth (d) as a function of drain spacing (L) and saturated thickness below the drains (D). This tables show values of d for a drain pipe with a radius (r_o) of 0.1 meter. Similar tables have been prepared for other values of r_o . For saturated thicknesses (D) greater than 10 meters, the equivalent depth can be calculated from drain spacing using the following equation:

$$d = 0.057 (L) + 0.845 \quad (5)$$

This equation was developed by linear regression from the values given in Table 2-1.

Table 2-1. Values for Equivalent Depth d (for $r_0 = 0.1$ m)
Calculated for Different Values of Drain Spacing (L)
and Saturated Thickness Below Drains (D)

$L \rightarrow$	5 m	7.5	10	15	20	25	30	35	40	45	50
D											
0.5 m	0.47	0.48	0.49	0.49	0.49	0.50	0.50				
0.75	0.60	0.65	0.69	0.71	0.73	0.74	0.75	0.75	0.75	0.76	0.76
1.00	0.67	0.75	0.80	0.86	0.89	0.91	0.93	0.94	0.96	0.96	0.96
1.25	0.70	0.82	0.89	1.00	1.05	1.09	1.12	1.13	1.14	1.14	1.15
1.50		0.88	0.97	1.11	1.19	1.25	1.28	1.31	1.34	1.35	1.36
1.75		0.91	1.02	1.20	1.30	1.39	1.45	1.49	1.52	1.55	1.57
2.00			1.08	1.28	1.41	1.5	1.57	1.62	1.66	1.70	1.72
2.25			1.13	1.34	1.50	1.69	1.69	1.76	1.81	1.84	1.86
2.50				1.38	1.57	1.69	1.79	1.87	1.94	1.99	2.02
2.75				1.42	1.63	1.76	1.88	1.98	2.05	2.12	2.18
3.00				1.45	1.67	1.83	1.97	2.08	2.16	2.23	2.29
3.25				1.48	1.71	1.88	2.04	2.16	2.26	2.35	2.42
3.50				1.50	1.75	1.93	2.11	2.24	2.35	2.45	2.54
3.75				1.52	1.78	1.97	2.17	2.31	2.44	2.54	2.64
4.00					1.81	2.02	2.22	2.37	2.51	2.62	2.71
4.50					1.85	2.08	2.31	2.50	2.63	2.76	2.87
5.00					1.88	2.15	2.38	2.58	2.75	2.89	3.02
5.50						2.20	2.43	2.65	2.84	3.00	3.15
6.00							2.48	2.70	2.92	3.09	3.26
7.00							2.54	2.81	3.03	3.24	3.43
8.00							2.57	2.85	3.13	3.35	3.56
9.00								2.89	3.18	3.43	3.66
10.00									3.23	3.48	3.74
∞	0.71	0.93	1.14	1.53	1.89	2.24	2.58	2.91	3.24	3.56	3.88

$L \rightarrow$	50	75	80	85	90	100	150	200	250
D									
0.5	0.50								
1	0.96	0.97	0.97	0.97	0.98	0.98	0.99	0.99	0.99
2	1.72	1.80	1.82	1.82	1.83	1.85	1.00	1.92	1.94
3	2.29	2.49	2.52	2.54	2.56	2.60	2.72	2.70	2.83
4	2.71	3.04	3.08	3.12	3.16	3.24	3.46	3.58	3.66
5	3.02	3.49	3.55	3.61	3.67	3.78	4.12	4.31	4.43
6	3.23	3.85	3.93	4.00	4.08	4.23	4.70	4.97	5.15
7	3.43	4.14	4.23	4.33	4.42	4.62	5.22	5.57	5.81
8	3.56	4.38	4.49	4.61	4.72	4.95	5.68	6.13	6.43
9	3.66	4.57	4.70	4.82	4.95	5.23	6.09	6.63	7.00
10	3.74	4.74	4.89	5.04	5.18	5.47	6.45	7.09	7.53
12.5		5.02	5.20	5.38	5.56	5.92	7.20	8.06	8.68
15		5.20	5.40	5.60	5.80	6.25	7.77	8.84	9.64
17.5		5.30	5.53	5.76	5.99	6.44	8.20	9.47	10.4
20			5.62	5.87	6.12	6.60	8.54	9.97	11.1
25			5.74	5.96	6.20	6.79	8.99	10.7	12.1
30							9.27	11.3	12.9
35							9.44	11.6	13.4
40								11.8	13.8
45								12.0	13.8
50								12.1	14.3
60									14.6
∞	3.88	5.38	5.76	6.00	6.26	6.82	9.55	12.2	14.7

Source: Wesseling, 1973.

2.1.3 Drains on Sloping Impervious Barriers

Typically, landfill cells are designed so that the compacted base of the cell slopes symmetrically at an angle towards the drains. A cross-section of such a design is shown in Figure 2-3. By designing the drain system on sloping barriers, the flow of water towards the collection system is accelerated, thus decreasing the steady-state head maintenance levels. This allows the drains to be spaced further apart or the heads to be lowered if the other parameters in the equation are held constant.

Drain spacing can be calculated for landfills designed with an impervious layer sloping towards the drains at an angle by the following equation (Moore, 1980):

$$L = (2h_{\max}/c)^{0.5} / [\tan^2 \alpha / c + 1 - (\tan \alpha / c) (\tan^2 \alpha + c)^{0.5}] \quad (6)$$

where:

$c = q/K$ (dimensionless)

α = slope angle (degrees)

h_{\max} = maximum allowable head level above impervious layer (m)

Note that because the "peak" formed by the two slopes between the drains intrudes on the saturated mound between the drains, h_{\max} is not found directly above this peak (midway between the drains) but at some distance to either side of this point.

For example, consider a landfill to be constructed in glacial till with bottom drains constructed of a material with a hydraulic conductivity (K) of 2×10^{-4} cm/sec (2×10^{-6} m/sec). The fill will have slopes toward the drains of 2% (1.1°), has an estimated leachate generation rate of 6 inches per year (4.2×10^{-4} m/day) based on water calculations, and must maintain the leachate level at a maximum elevation of 2 m above the drains. The drain spacing is calculated using equation 6:




Figure 2-3: Drains on Sloping Impervious Barriers

$$L = (2h_{\max}/c^{0.5}) / [\tan^2 \alpha/c + 1 - (\tan \alpha/c) (\tan^2 \alpha + c)^{0.5}] \quad (6)$$

$$\text{where } C = q/K = \frac{4.2 \times 10^{-4} \text{ m/day}}{2 \times 10^{-6} \text{ m/sec} \times 86,400 \text{ sec/day}} = 2.43 \times 10^{-3}$$

$$\begin{aligned} L &= \frac{(2 \times 2 \text{ m})}{(2.43 \times 10^{-3})^{0.5}} \left/ \left[\frac{(3.69 \times 10^{-4})}{(2.43 \times 10^{-3})} + 1 - \frac{(1.92 \times 10^{-2})}{(2.43 \times 10^{-3})} \right. \right. \\ &\quad \left. \left. + (3.69 \times 10^{-4} + 2.43 \times 10^{-3})^{0.5} \right] \right. \\ &= \frac{4 \text{ m}}{4.93 \times 10^{-2}} / [(1.52 \times 10^{-1}) + 1 - (7.90) (5.29 \times 10^{-2})] \\ &= 81.1 \text{ m} / 7.34 \times 10^{-1} \\ &= 110.6 \text{ m} \end{aligned}$$

These drainage system design equations assume that the drain pipe will accept the drainage water when it arrives at the drainline and that the drain pipe will carry away the water without a buildup in pressure. To meet the second assumption, the pipe size and drain slope must be adequate to carry away the water after it enters the drain pipe. The following sections describe the methods utilized to ensure that these assumptions are valid.

2.2 Drain Pipe Sizing

The design diameter of a drain pipe is dependent on the flow rate, the hydraulic gradient, and the roughness coefficient of the pipe. The roughness coefficient, in turn, is a function of the hydraulic resistance of the drain pipe. The formula for the hydraulic design of a drain pipe is based on the Manning formula for pipes which is:

$$Q_T = (R^{0.67})(i^{0.5}) A/n \quad (7)$$

where:

Q_T = design discharge (m^3/sec)

R = hydraulic radius of the pipe (m), which is equal to the wetted cross-sectional area divided by the wetted perimeter, or is equal to 1/4 of the diameter of a full flowing pipe

i = hydraulic gradient (dimensionless)

A = cross-sectional area of flow (m^2)

n = roughness coefficient (dimensionless).

Each of the above factors is described in further detail in the following sections.

2.2.1 Hydraulic Gradient (i) and Roughness Coefficient (n)

Subsurface drains are generally installed on a gradient (i) that is sufficient to result in a water velocity within the pipe that will prevent silting, but is less than the velocity which will cause turbulent flow. Past experience has shown that non-silting velocities occur above 1.4 feet per second (Soil Conservation Service, 1973). In situations where silting may be a problem and velocities are less than 1.4 ft/sec, filters and traps can be utilized to prevent the drains from clogging. The minimum hydraulic gradients required to prevent siltation in three sizes of closed pipe are listed in Table 2-2. However, steeper gradients are generally desirable provided they are less than the gradients which would result in turbulent flow.

To prevent turbulent flow, the hydraulic gradients should result in velocities that are less than critical velocities. Table 2-3 gives critical velocities for various drain sizes, gradients, and roughness coefficients. For smooth perforated concrete or plastic pipes, roughness coefficients can be assumed to be equal to 0.013 (Soil Conservation Service, 1973). Knowing the velocity which results in siltation and that which results in turbulent flow, the design engineer can select a gradient which results in a velocity somewhere between the two extremes.

TABLE 2-2. MINIMUM HYDRAULIC GRADIENTS FOR CLOSED PIPES

Pipe Diameter		Grade
Inches	Cm	%
4	10.2	0.10
5	12.7	0.07
6	15.2	0.05

Source: Soil Conservation Service, 1973

TABLE 2-3. DRAIN GRADES FOR SELECTED CRITICAL VELOCITIES

Drain Size Inches	V E L O C I T Y					
	1.4 fps ⁽¹⁾	3.5 fps	5.0 fps	6.0 fps	7.0 fps	9.0 fps
Grade - feet per 100 feet						
For drains with "n" = 0.011 ⁽²⁾						
Clay Tile, Concrete Tile, and Concrete Pipe (with good alignment)						
4	.28	1.8	3.6	5.1	7.0	11.5
5	.21	1.3	2.7	3.9	5.3	8.7
6	.17	1.0	2.1	3.1	4.1	6.9
8	.11	0.7	1.4	2.1	2.8	4.6
10	.08	0.5	1.1	1.5	2.1	3.5
12	.07	0.4	0.8	1.2	1.6	2.7
For drains with "n" = 0.013						
Clay Tile, Concrete Tile, and Concrete Pipe (with fair alignment)						
4	.41	2.5	5.2	7.5	10.2	16.8
5	.31	1.9	3.9	5.6	7.7	12.7
6	.24	1.5	3.1	4.4	6.0	10.0
8	.17	1.0	2.1	3.0	4.1	6.8
10	.12	.8	1.6	2.2	3.0	5.0
12	.09	.6	1.2	1.8	2.4	3.9
For drains with "n" = 0.015						
Corrugated Plastic Pipe						
4	.53	3.3	6.8	9.8	13.3	21.9
5	.40	2.5	5.1	7.3	9.9	16.6
6	.32	2.0	4.0	5.8	7.9	13.2
8	.21	1.3	2.7	3.9	5.3	8.8
10	.16	1.0	2.0	2.9	4.0	6.6
12	.13	.8	1.6	2.3	3.1	5.1

(1)—Feet per second

(2)—"n" is the roughness coefficient

Source: Soil Conservation Service, 1973.

2.2.2 Discharge (Q)

The design discharge of a pipe, Q_T is equal to the sum of the individual discharges which impinge upon the drain. Figure 2-4 shows the various flow components that could contribute to a drain discharge within a landfill. These flow components can be broken into two major categories--flow from within the site and flow from the surrounding aquifer.

In most instances the flow rates are estimated for design purposes so that the drain spacing can be determined using the previously presented equations. Estimates of discharge can be obtained using two simplified methods--the water balance method and the method of fragments. The water balance method is used to calculate the amount of the percolation that can recharge the water table between the lines of drains. This flow must be removed to maintain steady state conditions. A simple water balance equation is as follows:

$$q_p = P - RO - ST - ET$$

where:

q_p = percolation rate: amount of water that must be removed by drainage system (m/day)

P = precipitation (m/day)

RO = surface water runoff (m/day)

ST = change in soil (refuse) moisture storage (m/day)

ET = evapotranspiration rate (m/day)

Once the percolation rate has been calculated, discharge can be obtained by multiplying the percolation rate by the drainage area (i.e., Q_p (m³/day) = q_p (m/day) Area (m²)).

When using the water balance method to calculate flow rates or discharges for landfills, the following points should be considered:




Figure 2-4: Flow Components to a Zone of Saturation Landfill

- o Precipitation values for those time periods with high intensity rainfalls should be used to ensure percolation values are maximized and drainage design is adequate to handle these discharges.
- o Soil (refuse) moisture storage changes can be significant as new refuse is placed into the landfill; once field capacity of the materials is attained the ST term can be considered zero.
- o Variations in cover depths and the absence of vegetation can have significant effects on percolation rates; these effects will probably be greatest during the active operational phase when shallow covers are presented and drainage is inadequate.

The method of fragments is used to calculate the flow rates that are derived from the aquifer that borders the outermost drains. This flow component is not considered in the drain spacing equations but could significantly affect the pipe sizing of the border drain. Discharge of the border drains can be derived exclusively from horizontal flow or through a combination of horizontal and radial flow. Figure 2-5 shows the division of the border drain flow into two fragments that can be calculated separately and summed.

The quantity of flow into fragment 1 (Figure 2-5) can be estimated (Moulton, 1979) from the equation:

$$Q_{G1} = K(h^2)x/2(R_d - b) \quad (9)$$

where:

Q_{G1} = pipe discharge (m^3/day)

K = hydraulic conductivity (m/day)

h = height of the water table above the drain (m)

x = length of the drain (m)

R_d = distance of the drain's influence (m)

b = half the width of the drain and the trench (m).




Figure 2-5: Division of Symmetrical Drawdown Drain Problem into Two Equivalent Fragments (Moulton, 1979)

In order to solve the equation, the value of R_d must be known or estimated. Typically, the value of R_d is estimated using an equation such as the Sichardt (1940) equation:

$$R_d = C(h)(K)^{0.5} \quad (10)$$

where h and K are as specified as above, and C is a constant that Sichardt set equal to 3; however, most drainage engineering books now recommend this constant be set at 1.5-2 for "realistic" results.

The quantity of flow into fragment 2 can be estimated (Moulton, 1979) from the equation:

$$Q_{G2} = (K(H-D)x)/[R_d/D] - (1/\pi)(\log 0.5(\sinh \pi/D)) \quad (11)$$

where the new terms are:

H = height of water table above impervious barrier (m)

D = height of the drain above impervious barrier (m)


Once the individual discharges for the segments are calculated, the total discharge is the sum of the individual discharges. For sites on impervious barriers, the total discharge is equal to Q_{G1} ; for sites with drains above an impermeable barrier the total discharge is the sum of Q_{G1} plus Q_{G2} .

2.2.3 Pipe Size

Once the total discharge (Q_T) has been determined, an appropriate grade selected, and the appropriate roughness coefficient determined, the minimum drain diameter can be determined. Nomographs such as the one shown in Figure 2-6 are typically utilized to obtain pipe diameters. Because the nomographs are based on the Manning formula (Equation 7), this formula can be used directly to obtain pipe size. Rearranging Equation 7, pipe diameter (d) can be found from:

$$d = 4(Q_T n / i)^{0.5} 1.5 \quad (12)$$

DRAIN CAPACITY CHART - $n = 0.013$



REFERENCE: This chart was developed by Guy B. Fassen.

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
ENGINEERING DIVISION - DRAINAGE SECTION

STANDARD DWG. NO.
ES - 721
SHEET 2 OF 3
DATE 8-3-70

Figure 2-6. Capacity chart - $n = 0.013$

Source: Soil Conservation Service, 1973.

A margin of safety is usually incorporated in the selected drain diameter which will account for the reduction in drain capacity caused by siltation over time and for any discharge in excess of the design capacity. Because the nomographs and Manning formula estimate drain diameter without accounting for a margin of safety, the drain diameter is typically chosen as the next larger size.

2.3 Filters and Envelopes

Performance of a drainage system is based on the assumption that the pipe will accept all inflow without a pressure build-up. Filters and envelopes are used to ensure that this requirement is met.

2.3.1 Function of Filters and Envelopes

The primary function of a filter is to prevent soil particles from entering and clogging the drain. The function of an envelope is to improve water flow into the drains by providing a material that has a higher permeability than the surrounding soil. Envelopes may also be used to provide suitable bedding for a drain and to stabilize the soil material on which the drain is being placed. The filter's function and the envelope's function are somewhat contradictory because filtering is best accomplished by fine materials, and coarse materials are more appropriate for envelopes.

As percolating water approaches a subsurface drain, the flow velocity increases as a result of convergence towards the perforations or joints in the pipe. This increase in velocity is accompanied by an increased change in hydraulic gradient. As a result, the potential for soil particles to move towards the drain is increased. By using a highly permeable envelope material around the pipe, the number of pore connections at the boundary between the soil and the envelope will increase, thereby decreasing the hydraulic gradient.

A filter should prevent the entry of soil particles, which could result in sedimentation and clogging of the drains, blocking of

perforation or tile joints, or blocking of the envelope. The filter materials should not, however, be so fine that they prevent all soil particles from passing through. If silts and clays are not permitted to pass through, they may clog the envelope resulting in increased entrance resistance which can cause the water level to rise above the drain.

Although filters and envelopes have different distinct functions, it is possible to meet the requirements of both a filter and an envelope by using well-graded sands and gravels. The specifications for granular filters, however, are more rigid than those for envelopes. It is usually necessary for filter materials to be screened and graded to develop the desired gradation curves. Envelope materials, on the other hand, may have a wide range of allowable sizes and gradings (Soil Conservation Service, 1973).

2.3.2 Design of Sand and Gravel Filters

Detailed design procedures are available for both gravel and sand envelopes. The Soil Conservation Service (SCS) (1973) has distinct design criteria for filters and envelopes, whereas the Bureau of Reclamation (1979) has developed one set of standards for a well-graded envelope which meets the requirements of both a filter and an envelope. The separate SCS design criteria will be considered below for the following reasons:

- o Site specific conditions may warrant the use of only a filter or an envelope, but not both.
- o Where both a filter and an envelope are needed, the SCS design criteria for a filter can generally be used.
- o It may be desirable to use a fabric filter with a gravel envelope.

The approach recommended by SCS is to determine whether the drainage system needs a filter and then determine the need for an envelope. Generally, this sequence is performed because a well-graded filter can also function as an envelope.

The general procedure for designing a gravel filter is to (1) make a mechanical analysis of both the soil and the proposed filter material; (2) compare the two particle distribution curves; and (3) decide by some set of criteria whether the envelope is satisfactory. The Corps of Engineers and the Soil Conservation Service (1973) have adopted similar criteria which set size limits for a filter material based on the size of the base material. These limits are:

$$\frac{\text{50 percent grain size of the filter}}{\text{50 percent grain size of the base}} = 12 \text{ to } 58$$

$$\frac{\text{15 percent grain size of the filter}}{\text{15 percent grain size of the base}} = 12 \text{ to } 40$$

Multiplying the 50 percent grain size of the base material by 12 and 58 gives the limits within which the 50 percent grain size of the filter should fall. Multiplying the 15 percent grain size of the base material by 12 and 40 gives the limits within which the 15 percent grain size of the filter should fall.

All of the filter material should pass the 1.5 inch sieve, 90 percent of the material should pass the 0.76-inch sieve, and not more than 10 percent of the material should pass the No. 60 sieve. The maximum size limitation aids in preventing damage to drains during placement, and the minimum size limitation aids in preventing an excess of fines in the filter which can clog the drain. When the filter and base materials are more or less uniformly graded, a generally safe filter stability ratio of less than 5 is recommended.

$$\frac{\text{15 percent filter grain size}}{\text{85 percent filter grain size}} = 12 \text{ to } 58$$

Consideration must also be given to the relationship between the grain size of the filter and the diameter of the perforations in the pipe. In general, the 85 percent grain size of the filter should be no smaller than one-half the diameter of the perforations. SCS recommends a minimum filter thickness of 8 cm (3 inches) or more for sand and gravel envelopes (Soil Conservation Service, 1973).

2.3.3 Design of Sand and Gravel Envelopes

The first requirements of sand and gravel envelopes is that the envelope have a permeability higher than that of the base material. SCS (1973) generally recommends that all of the envelope material should pass the 1.5-inch sieve, 90 percent should pass the 0.75-inch sieve, and not more than 10 percent should pass the No. 60 sieve (0.25 millimeter). This minimum limitation is the same for filter materials; however, the gradation of the envelope is not important since it is not designed to act as a filter.

The optimum thickness of envelope materials has been a subject of considerable debate. Theoretically, by increasing the effective diameter of a pipe, the amount of inflow is increased. If the permeable envelope is considered to be an extension of the pipe, then the larger the envelope's thickness the better. There are, however, practical limitations to increasing envelope thickness. The perimeter of the envelope through which flow occurs increases as the first power of the diameter of the envelope, while the amount of the envelope material required increases as the square of the diameter. Doubling the diameter of the envelope (and consequently decreasing the inflow velocity at the soil-envelope interface by half) would require four times the volume of envelope material with an attendant increase in costs. Recommendations for drain envelope thickness have been made by various agencies. The Bureau of Reclamation (1978) recommends a minimum thickness of 10 centimeters (4-inch) around the pipe. SCS (1973) recommends an 8 centimeter (3-inch) minimum thickness.

2.3.4 Synthetic Filters

For synthetic materials, the suitability of a filter can be determined from the ratio of the particle size distribution to the pore size of the fabric. The accepted design criterion for geotextile filters is:

$$\frac{\text{P85 (85\% pore size of the filter fabric)}}{\text{D85 (85\% grain size of the subgrade material)}} = \leq 1$$

$$\text{or } P85 \leq D85$$

Using this equation, the P85 of the filter fabric can be determined from the D85 of the subgrade soil. Manufacturers of geotextile fabrics can then be consulted to select the proper filter type (DuPont Co., 1981).

3.0 DESIGN AND CONSTRUCTION

This chapter presents an analysis of a hypothetical zone of saturation landfill site that is based on data provided by the State of Wisconsin. A sensitivity analysis was performed for the site (based on the equations presented in Chapter 2) using the following parameters:

- o Groundwater/leachate generation rates, q
- o Hydraulic conductivity of waste materials, K_1 and native soils, K_2
- o Head maintenance levels within the site, h
- o Drain spacing, L

Also included in this chapter are design and construction considerations which may be incorporated into a zone of saturation landfill.

3.1 Hypothetical Site

A hypothetical zone of saturation landfill site was developed using available data from similar sites located in Wisconsin. A cross-section of this site is presented in Figure 3-1. Table 3-1 presents some of the typical ranges of values that may be encountered at similar sites. The hypothetical site and the accompanying site data are used in the next section as the basis for the sensitivity analysis. Assumptions made to simplify the site conditions include:

- o Landfill materials and soils are homogeneous and isotropic.
- o Water tables within and outside the site are drawn down to drain level.
- o Groundwater system is at equilibrium (steady state) conditions.
- o Groundwater pressures in the underlying (dolomite) aquifer do not affect groundwater movement into the bottom of the pit.




Figure 3-1: Cross Section of Hypothetical Zone of Saturation Landfill

TABLE 3-1. RANGE OF SITE VARIABLES

Parameter	Range of Values
Cell Dimensions	
o Depth of cell	20 to 30 feet (average) up to 60 feet
o Thickness of compacted clay beneath drains	3 to 5 feet
o Thickness of compacted clay sidewalls	5 feet (average)
o Thickness of clay till below base grade	20 to 30 feet (minimum) usually greater than 50 feet
o Drain spacing	200 to 400 feet
Hydraulic Data	
o Depth to water table	10 feet (average)
o Permeability of:	
Clay till	10^{-5} to 10^{-7} cm/sec
Refuse	10^{-2} to 10^{-5} cm/sec
Compacted clay	$\leq 10^{-7}$ cm/sec
o Drain diameters	4 to 6 inches
o Slope of base	1% (average)

If these assumptions are invalid, the drain equations will predict drain spacings that are too large. The degree to which these equations over-predict will be directly related to the degree the assumptions are invalid.

3.2 Sensitivity Analyses

Sensitivity analyses were performed on the drain equations for:

- o Drains on impervious barriers
- o Drains on sloping impervious barriers
- o Drains above impervious barriers.

The variables in the sensitivity analyses include head maintenance levels, hydraulic conductivities, flow rates, drain spacing and barrier slope.

3.2.1 Drains on Impervious Barriers

The equation for drains placed on an impervious barrier is (Equation 2, Chapter 2):

$$L = (4K_1 h^2 / q)^{0.5} \quad (2)$$

When using this equation, a barrier is usually considered impervious if the barrier material has a permeability (K_2) at least 10 times less than the overlying material (K_1). This situation typically occurs in landfills that have recompacted clay bases.

Table 3-2 presents the results obtained when equation 2 is solved for drain spacing (L) using various values of flow rates (q), head maintenance levels (h), and hydraulic conductivities (K_1) of the landfill material. A log-log plot of drain length versus flow rate for four hydraulic conductivities (holding the head level constant at one meter) is shown in Figure 3-2. Table 3-2 and Figure 3-2 show how the proper drain spacing (L) is directly related to head maintenance levels (h), inversely related to the square root of the leachate generation rate (q), and directly related to the square root of the landfill permeability (K_1).

TABLE 3-2. DRAIN LENGTH SPACING (m) FOR DRAINS ON AN IMPERMEABLE BARRIER

q (m/day)	h=6(m)				h=4(m)				h=2(m)				h=1(m)				h=0.5(m)			
	K(cm/sec)																			
	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵
0.5	157	50	16	5	105	33	11	3	52	17	5	2	26	8	3	1	13	4	1	> 1
0.01	353	111	35	11	235	74	23	7	118	37	12	4	59	19	6	2	29	9	3	1
0.005	499	157	50	16	333	105	33	11	166	52	17	5	83	26	8	3	42	13	4	1
0.001	1115	353	111	35	744	235	74	23	371	118	37	12	186	59	19	6	93	29	9	3
0.0005	1577	499	157	50	1052	333	105	33	525	166	52	17	263	83	26	8	131	42	13	4
0.0001	3527	1115	353	111	2352	744	235	74	1174	371	118	37	588	186	59	19	294	93	29	9
0.00005	4989	1577	499	157	3328	1052	333	105	1661	525	166	52	831	263	83	26	416	131	42	13

Isobar equal to 122 meters (400 ft.): maximum l for theoretical site




Figure 3-2. Drain Length versus Flow Rates for Head Levels Equal to 1-meter

Leachate generation rate (q) and landfill permeability (K_1) are the most important parameters to determine accurately when designing a landfill, not because they are the most sensitive, but because they are the most difficult to determine accurately. Head maintenance levels are usually predetermined in the landfill design and therefore are not sensitive even though they potentially can have the greatest effect on drain spacing.

One aspect of the equation for drains on impervious barriers that is not readily apparent is that this equation can also be used for determining the depth of drainage blankets. When the equation is utilized for this purpose, the height of the water table is designed to remain within the blanket. Permeabilities of the drainage blanket materials are also generally known with some accuracy, which is not the case with most landfill materials. Table 3-2 also shows the combination of flow rates, hydraulic conductivities, and head maintenance levels that yield drain spacings that are equal to or less than the maximum spacing used in the hypothetical site (i.e., 400 ft). Generally, when flow rates are large and hydraulic conductivities are low, the theoretical upper limit of 400 feet on drain spacing is too large to accomplish the intended design. It is, therefore, important to quantify the values associated with leachate generation rates and landfill permeabilities to determine drain spacing; drain spacing should not be specified arbitrarily.

3.2.2 Drains on Sloping Impervious Barriers

Drains that are placed on sloping impervious barriers are governed by:

$$L = (2h/c^{0.5}) / [(\tan^2 \alpha/c) + 1 - (\tan \alpha/c)(\tan^2 \alpha+c)^{0.5}] \quad (6)$$

As discussed in the previous section, the underlying drain material is typically considered impermeable if its permeability is at least ten times less than the permeability of the overlying material. This situation is typical of landfills that have compacted clay bases.

Table 3-3 gives solved values of h/L for selected values of $c = q/K_1$ and barrier slope angles, α . Figure 3-3 presents a plot of h/L versus $I = \tan \alpha$ for selected values of $c = q/K_1$. This graph shows how h/L is indirectly related to the barrier slope angle and directly related to $c = q/K_1$. Generally, the greatest decrease in h/L occurs when the barrier angle increases from zero to five degrees (i.e., up to approximately 10% slope). Angles greater than five degrees cause decreasingly smaller changes in h/L . For design purposes, this means that increasing the angle above five degrees has little effect on head maintenance levels (h) and drain spacing (L).

Using the values of h/L presented in Table 3-3, drain spacing was solved while holding head maintenance levels (h) constant at two meters. Table 3-4 presents the results of this analysis, and Figure 3-4 shows a plot of drain length versus $c = q/K_1$ for barrier angles of 0° , 1° and 5° . These data show that if h is held constant, the barrier angle has the greatest effect on increasing drain spacing length at lower values of $c = q/K_1$ (i.e., low leachate generation rates divided by high permeabilities).

The equation for drains on an impermeable sloping barrier can also be utilized for determining the thickness of a drain blanket by substituting h for the thickness of the drain blanket (i.e., so that the maintenance head level is designed to be within the blanket) and K_1 for the permeability of the drain blanket. For example, consider a landfill without a drainage blanket with the following parameters: $q = 0.0005$ m/day, $K_1 = 0.00864$ m/day (i.e., 10^{-5} cm/sec), $\alpha = 1^\circ$, and $h = 2$ meters. Based on these figures, drains would have to be spaced at intervals of $L = 18$ meters to maintain a 2-meter head level. If a drainage blanket that has a permeability of $K_1 = 0.864$ m/day (10^{-3} cm/sec) is installed at the site and the values of q and L remain unchanged, the thickness of the blanket and hence the corresponding height of the head levels would be 0.14 meters. This is a substantial reduction in head levels for a relatively thin drain layer. The advantage to lowering the head level within the site is that less leachate is likely to be released from the site.

TABLE 3-3 VALUES OF h/L FOR VARIOUS $C=q/K_1$ AND ANGLES α

$C=q/K_1$	α (degrees)					
	0	0.5	1	2	3	5
5.787	1.203	1.198	1.194	1.186	1.177	1.161
0.5787	0.380	0.376	0.372	0.364	0.356	0.341
0.05787	0.120	0.116	0.112	0.105	0.101	0.092
0.005787	0.038	0.034	0.031	0.027	0.024	0.022
0.0005787	0.012	0.009	0.008	0.007	0.006	0.006




Figure 3-3. Plot of h/L versus $I = \tan \alpha$ for drain and sloping impervious layers (Moore, 1980)

TABLE 3-4 DRAIN SPACING (m) FOR HEAD MAINTENANCE LEVELS OF 2-METERS

$c=q/K_1$	α (degrees)			
	0	1	3	5
5.787	1.66	1.68	1.70	1.72
0.5787	5.26	5.38	5.62	5.87
0.05787	16.67	17.86	19.80	21.74
0.005787	52.63	64.52	83.33	90.91
0.0005787	166.67	250.00	317.40	326.60




Figure 3-4. Drain Length (L) versus $c=q/K_1$ for α equal to 0° , 1° , and 5° .

3.2.3 Drains Above an Impervious Barrier

The governing equation for a drain system above an impervious barrier is:

$$L = [(8K_2dh + 4K_1h^2)/q]^{0.5} \quad (3)$$

where the parameters are as defined previously in Chapter 2.

This equation takes into account radial flow to the drains through the material underlying the drain.

Solutions to the equation are shown in Table 3-5 for a head maintenance level (h) of two meters, a permeability (K_1) of the landfill material of 0.00864 m/day (i.e., 10^{-5} cm/sec), and a depth to the impermeable layer (D) of 30.4 meters. Figure 3-5 shows a plot of drain spacing (L) versus inflow rates (q) for various permeabilities of underlying material (K_2). These presentations show that when the permeabilities of the overlying (K_1) and the underlying (K_2) material are the same, the drain spacing (L) increases. This phenomenon is caused by the introduction of radial flow to the drains rather than straight lateral flow.

When the permeability of the underlying material (K_2) is an order of magnitude (0.1) less than the overlying material (K_1), the calculated drain spacing does not differ significantly from a drain on an impermeable barrier. If the underlying material has a permeability that is two orders of magnitude (0.01) less than the overlying material, the drain spacing is identical to a drain on an impermeable barrier. This occurs because the term $8K_2dh$ does not significantly affect the results of the drain spacing equation. Consequently, the "rule of thumb" for designing drains is that if the underlying layer has a permeability at least 10 times less than the overlying material, the underlying material can be considered impermeable.

3.3 Application

The basic premise behind the use of a landfill located in the zone of saturation is that if the head maintenance levels within the site are

TABLE 3-5 DRAIN SPACING (m) FOR DRAINS ABOVE AN IMPERMEABLE
BARRIER ($h=2\text{m}$, $K_1=0.00864 \text{ m/day}$ (10^{-5}cm/sec), $D=30.4\text{m}$)

q (m/day)	K_2 (cm/sec)			
	10^{-5}	10^{-6}	10^{-7}	Impermeable
0.05	2	2	2	2
0.01	5	4	4	4
0.005	7	5	5	5
0.001	19	12	12	12
0.0005	31	18	17	17
0.0001	114	43	37	37
0.00005	212	64	52	52




Figure 3-5. Drain Spacing (L) versus inflow rates (q) where $h=2$ meters and $K_1=10^{-5}$ cm/sec.

less than the groundwater levels outside the site, then hydraulic gradients should be into the site, thus minimizing the likelihood of contaminant release. Basic hydraulic principles show this to be the case as long as (1) the landfill materials and soils are homogeneous and isotropic, (2) water tables are drawn down to drain levels, and (3) the groundwater system is at equilibrium. In reality, these conditions rarely exist at a landfill site. For these real-world situations, the Wong (1977) model can be used to predict releases.

3.3.1 Parameter Estimation

In order to utilize the drain spacing equations, the input parameters must be known with some accuracy. The two parameters which are the most difficult to estimate accurately are leachate generation rate (q) and hydraulic conductivity (K). Head maintenance level (h) and barrier slope angle (α) are typically chosen by the designer and are not estimated.

Total inflow rates to the drains can be estimated through the use of water balance equations (equation 8) and the method of fragments (equations 9 and 10). These equations, however, do not take into account the volume of liquid that is added to the site as landfill material (e.g., paper waste sludges). Estimating this volume is very specific to a landfill. Once the total volume is estimated, the value should probably be increased to take into account variations that were not anticipated (e.g., acceptance of more liquids, unseasonably high precipitation) and to add a margin of safety to the design.

Determining the hydraulic conductivity of the landfill material with any accuracy is very difficult because, typically, the material is a mixture of wastes and daily covers which tends to create discrete cells. Waste mixtures tend to cause the landfill to be very heterogeneous and anisotropic, making estimations of permeabilities difficult. Here, as before, the hydraulic conductivity selected should probably be the highest value found for the waste materials. The problems associated with daily cover can be minimized if the cover is removed each day, allowing old and new fill materials to be hydraulically connected.

The use of drainage blankets in a landfill effectively eliminates the problem associated with determining conductivities. Hydraulic conductivities for the drainage blanket can be determined easily in the lab and most blanket materials are relatively homogeneous and isotropic. A blanket layer covering the bottom of the cell and the sidewalls provides a hydraulic connection between the leachate generated and the drains. A drainage blanket also aids in the prevention of leachate pooling, accelerates leachate removal times, and allows for lower head maintenance levels with the same drain spacing.

3.3.2 Landfill Size

Technically a landfill is depth-limited in a zone of saturation setting only by the propensity of the sidewalls for slumping or failure. Theory shows that lower base grades in the fill result in higher hydraulic gradients into the site. These higher gradients will result in larger quantities of groundwater that must be removed from the site. Problems can arise, however, if the base grades are extended deep enough to cause quick conditions in the base or if the base intercepts an aquifer that has a lower head level than the overlying aquifer. If quick conditions occur, extensive dewatering may be necessary to maintain a stable base. If the base extends into an underlying aquifer with a lower head level, contamination of the aquifer is likely when the pit is filled. The areal extent of the landfill is generally not considered limiting if the drainage system is functioning properly.

3.3.3 Example Problem

An example of the use of the drain equations for the hypothetical site developed in Section 3.2 is presented here for illustrative purposes. Table 3-6 presents the data utilized in the example. For the example, the recompacted clay base and sidewalls were assumed to have the same permeabilities as the saturated clay aquifer.

To calculate the drain spacing needed at the site, the equation for drains on sloping barriers (equation 6) can be used because the

TABLE 3-6. EXAMPLE DATA SET

Parameter	Value
Cell Dimensions	
o Width	1000 ft (304m)
o Length	1000 ft (304m)
o Depth	30 ft (9.1m)
Clay Thickness Below Base	50 ft (15.2m)
Hydraulic Conductivities	
o Fill (K_1)	10^{-5} cm/sec (0.00864 m/day)
o Clay (K_2)	10^{-7} cm/sec (0.0000864 m/day)
- compacted or natural	
Base Grade	1% (0.6 degrees)
Water Table (b.l.s.)	10 ft (3.0m)
Head Maintenance Levels	10 ft (3.0m)
Inflow (q) From Percolation	10 in/yr (0.0007 m/day)

underlying clay material has a permeability of 10 times less than the fill material. Solving equation 6 for drain spacing (L):

$$\begin{aligned}
 L &= (2h/c^{0.5}) / [(\tan^2 \alpha/c) + 1 - (\tan \alpha/c)(\tan^2 \alpha+c)^{0.5}] \\
 c &= q/K_1 \\
 &= 0.0007(\text{m/day})/0.00864(\text{m/day}) \\
 &= 0.08102 \\
 L &= (2(3.0)/0.08102^{0.5}) / [\tan^2 0.6/0.08102 + 1 - (\tan 0.6/0.08102) \\
 &\quad [(\tan^2 0.6 + 0.08102)^{0.5}]] \\
 &= (21.079) / [(0.00135) + 1 - (0.12926)(0.28483)] \\
 &= 21.85\text{m}(71.89 \text{ ft})
 \end{aligned}$$

The value obtained for drain spacing using these parameters is significantly less than the currently specified allowable upper limit (about 400 ft). However, this solution would not be considered conservative for an actual site where (1) conductivities of the fill may not be a uniform 10^{-5} cm/sec, (2) inflow rates may be higher than expected; for example, when the site is not capped, and (3) materials with high water content may be landfilled.

An appropriate pipe size can be selected by calculating the system's expected discharge and considering the factors described in Section 2. Total flow along any single collector pipe can be calculated by:

$$Q_1 = qA$$

where q, inflow, is 0.0007 m/day and A, area, is the area drained by each drain line—22m x 304m (drain spacing times length)

$$\begin{aligned}
 Q_1 &= (0.0007 \text{ m/day})(22\text{m})(304\text{m}) \\
 &= 4.7 \text{ m}^3/\text{day} \quad (0.002 \text{ ft}^3/\text{sec})
 \end{aligned}$$

Using Figure 2-6 for plastic pipes with a roughness coefficient of $n = 0.013$ and a design velocity of 1.4 ft/sec, a 4-inch drain pipe should be sufficient to handle the discharge. Total discharge from the main header pipe is:

$$\begin{aligned}
 Q_T &= qA \\
 &= (0.0007 \text{ m/day})(304\text{m})(304\text{m}) \\
 &= 64.7 \text{ m}^3/\text{day} \text{ (0.026 ft}^3/\text{sec or 17,094 gal/day)}
 \end{aligned}$$

Using Figure 2-6 again, a 4-inch pipe should be sufficient to handle the flows. A larger size pipe may be selected as a margin of safety.

3.4 Construction Aspects

Previous discussions related the application of the design criteria for zone-of-saturation landfill leachate collection systems to a hypothetical site. Some aspects of construction of these sites are important but do not fall within the focus of the other sections. These considerations are described in the following sections and include:

- o Construction inspection
- o Collector drain maintenance
- o Future operating conditions

3.4.1 Construction Inspection

Construction inspections are important to ensure the specified design criteria are implemented in the field. Some criteria which are important for zone of saturation landfills are:

- o Moisture of clays when compacted on bases and sidewalls
- o Placement of drain pipe and filter envelopes, and their protection while exposed
- o Compliance with specified design criteria for slopes, and drain blanket thickness and gradation

The clay tills associated with the zone of saturation landfills can easily exceed the moisture content at which maximum density can be achieved. Trying to compact these excessively wet clays on the base and sidewalls of the landfill is a wasted effort, and in many instances, causes the soil to shear. Shearing of the clays may result in planes of weakness and cracks throughout the layer which can easily transmit

leachate out of the cell. Construction inspections can identify when the soils exceed the optimum moisture content for compaction and prevent their placement until the clays have dried to within an acceptable moisture content range.

Construction inspections should be performed during drain pipe and filter envelope placement. Inspections can ensure that these operations are performed as specified in the designs and that:

- o Drain pipes are not damaged during placement
- o Filter materials are kept free of fines and are graded and installed properly
- o Drains are protected after placement so that fines do not clog drains before wastes are placed

Slopes specified within a cell are generally just enough to prevent pooling of leachate on the compacted clay base (i.e., 1% slope). With these gentle slopes, there is a very small margin for error that would still ensure that leachate moves freely towards the drain. Inspections performed during the grading of the base can verify proper construction. Inspections should also be performed during the placement of a drain blanket to ensure adequate blanket thickness and proper gradation of the blanket material.

3.4.2 Drain System Maintenance

Proper maintenance of a drain system is a critical element in ensuring its continued performance. The initial design of the system must allow for adequate access to the drain system components both for inspections and cleanings. Regular maintenance inspections should be performed to assess the system's performance and to plan cleaning and repairing activities. Additionally, maintenance inspections should be performed when an unexplained reduction in flow occurs to sumps or increased head levels are observed within the cell.

3.4.3 Future Operating Conditions

Landfill designs should anticipate and account for the type of waste disposal operations planned. As mentioned previously, hydraulic conductivities of the wastes placed in a cell are critical to the design of the leachate collection system. Conductivities used for design purposes are frequently estimates based on the experience of the designer or are averages that represent the range of conductivities that could be found throughout the cell. If the landfill will be accepting balings, shreddings, large solid objects, or separations of particular wastes during its operational life, the conductivities used in the drain designs should be adjusted to reflect the hydraulic conductivity of these materials and their volume in relation to the remainder of the fill material.

The total quantity of water that must be extracted from zone of saturation landfills can vary widely. Water can be derived from percolating rainfall, groundwater infiltration, and from sludges or liquids brought into the site. Underestimating the amount of water that must be removed will result in rising internal head levels and the eventual release of generated leachate. Therefore, care must be exercised to ensure that water removal capabilities specified in the landfill design realistically represent the eventual landfill operations.

4.0 FLOW NET ANALYSIS

4.1 Introduction

Water flow through porous media is governed by several physical relationships (e.g., Darcy's Law) that can also be represented mathematically. The equations used to represent this flow can be arranged so that they apply to certain physical conditions. The solutions to the equations can then be obtained through numerical or graphical means; the graphical solutions are called flow nets. In this case, the flow nets are graphical representations of two-dimensional equations of continuity for water flow.

The generation and application of a flow net requires certain assumptions and simplifications. Most of these are common to any representation (model) of a natural physical system and include the assumptions of aquifer homogeneity, water incompressibility and laminar Darcian flow. Consideration of site conditions at each of three Wisconsin landfills reveals several features which are common to all, so that the flow nets can be constructed for a generic site that incorporates these common features (Figure 4-1) and also includes some simplifications. These include:

- a) elimination of small heterogeneities in the clay around the site, since they are discontinuous and not well-mapped.
- b) treatment of the underlying dolomite as an impermeable boundary. It is recognized that recharge to the clay probably does occur from the dolomite; however, the vertical permeability of the clay is low enough that this recharge can be considered negligible for the purposes of constructing a flow net.
- c) treatment of all landfill surfaces as orthogonal to ground surface.
- d) assuming that the landfill excavation can be treated as a circular well so that water flows radially to it.




FIGURE 4-1. CROSS SECTION OF TYPICAL ZONE-OF-SATURATION LANDFILL

- e) assuming that the water table aquifer can be treated as a line source of seepage beyond 250 feet from the landfill.

The flow nets are composed of two families of lines that intersect at right angles. Flow lines show paths along which water can flow; equipotential lines represent lines of equal hydraulic head. The flow nets constructed for the generic site indicate the approximate arrangement of flow lines and equipotential lines around the landfill for different physical conditions, as explained below.

4.2 Initial Conditions

Three points need to be made about the flow nets before examination. First, by treating the excavation as a circular well, some idea of the radius of influence (R_o) and equivalent well radius (R_w) can be obtained. These are defined by:

$$R_w = \sqrt{\frac{LW}{\pi}} \quad \text{where } L = \text{length of landfill} \\ W = \text{width of landfill}$$

Values of L and W were chosen equal to 300 ft. so that $R_w = 169$ ft.

$$R_o = C\Delta h \sqrt{\frac{K}{10^{-4}}} \quad \text{where } C = \text{a constant ranging from 1.5 to 3} \\ \Delta h = \text{drawdown expected in "well"} \\ K = \text{hydraulic conductivity in cm/sec}^{-1}$$

Values chosen for Δh (30 feet) and K (1×10^{-5} cm/sec⁻¹) represent typical values for these parameters at each site. Several references used suggested setting $C = 2.0$ for typical results. This gives $R_o = 19$ feet.

Second, there is a difference between the horizontal and vertical hydraulic conductivities at these sites because of the layered nature of the till deposits. Average values for horizontal K and vertical K used here were 1×10^{-5} cm/sec⁻¹ and 2×10^{-7} cm/sec⁻¹, respectively. Construction of flow nets for anisotropic media requires that the horizontal and/or vertical dimensions be transformed to offset the effect of different horizontal and vertical hydraulic conductivities.




FIGURE 4-2. INFLOW TO TYPICAL LANDFILL CELL (PLAN VIEW)

4.3 Parameter Analysis

Examination of the effect of leachate maintenance levels (Figures 4-3A, B, C) indicate that the most favorable situation in terms of collecting lower amounts of leachate is when the maintenance level is relatively high. This causes redistribution of the equipotential lines in the aquifer around the drains such that the contribution of inflow from the aquifer is small compared to that from the leachate. However, this does not leave much of a safety margin and also enhances the susceptibility for outward leakage along permeable sandy lenses in the sides of the landfill.

Analysis of the effect of vertical gradients (Figures 4-4A, B) indicates that, in comparison to sidewall inflow and leachate from the refuse, the amount of inflow at the base will be small regardless of the direction of gradient. This is predominantly due to the low vertical hydraulic conductivity of the clay till in contrast to the more permeable sidewalls.

Analysis of the effect of drain spacing (Figure 4-5) shows that the drains tend to depress equipotential lines between their centers, bringing higher head levels closer to the bottom of the excavation. In the presence of a local downward gradient, this might enhance the possibility of diffusion of contaminants through the base of the fill, although most movement would be horizontal because of aquifer anisotropy. As the number of drains increases, this effect becomes less noticeable, and at some point would be offset by inflow through the base of the excavation.

The effect of the depth of excavation below the water table can also be examined by using some of the assumptions and site dimensions given earlier and treating the excavation as a well. If the leachate maintenance level is set at the base of the fill, the amount of inflow in relation to excavation depth varies as follows:




FIGURE 4-3. FLOW NETS WITH DIFFERENT LEACHATE LEVELS




FIGURE 4-4. FLOW NETS WITH DIFFERENT VERTICAL GRADIENTS




FIGURE 4-5. FLOW NETS WITH DIFFERENT NUMBERS OF DRAINS

<u>Depth Below Water Table Excavated, Ft.</u>	<u>Approximate Inflow, GPM</u>
10	8.8
20	16.7
30	23.8
40	29.8

These inflows need to be considered in comparison to the capacity of the drain system and the possible inducement of heaving or buckling because of the artesian head in the underlying dolomite. Rough calculations indicate that 40 feet is about the maximum depth that should be excavated, less if the remaining depth to the dolomite is below about 50 feet.

5.0 MODELS

This chapter characterizes some commonly accepted models that can be utilized in the design and performance evaluation of waste disposal sites, and in the tracking of pollutants released from these sites. These models are divided into two major groups: (1) release rate models and (2) solute transport models. Typically, estimates of leachate quantity and quality released from a site are obtained from a release rate model and are used as input to a solute transport model. The theory behind some of the models is very complex and readers should refer to other sources such as Bachmat et. al. (1980), Mercer and Faust (1981), Anderson (1979), and Weston (1978) for in-depth discussions of modeling.

5.1 Release Rate Models

The first and probably the most crucial step in waste site modeling is to obtain accurate estimates of the quantity and quality of leachate that will be released into the subsurface environment. Only after adequate determination of leachate release can a solute transport model be performed. This section briefly describes the theory behind release rate models and presents those models that can potentially be utilized in obtaining release rates from landfills.

5.1.1 Fundamentals

Most release rate models are based on dividing the problem of prediction into three separate components--leachate generation, constituent concentrations, and leachate release rates from the site. Combining the three separate components allows for prediction of the quantity and quality of leachate that can be expected to be released from the site.

5.1.1.1 Leachate Generation

Leachate generation refers to the quantity of fluid within the site available to leach and transport waste constituents. The major factors that directly influence leachate generation are listed in Table 5-1. Probably the most important factors for zone-of-saturation landfills are infiltrating precipitation and groundwater intrusion. There are currently two main approaches for predicting leachate generation--the water balance approach and the use of bounding assumptions.

Fenn, Hanley, and DeGeare (1975) pioneered the use of water balances to predict leachate generation from solid waste disposal facilities based on the earlier work of Thornthwaite (1955). Several authors have since updated and modified Fenn, et al.'s., work for application to other types of waste disposal sites. Basically, water balances numerically partition the amount of fluid moving into, around, and through the cap of a land disposal facility by utilizing the equation:

$$\text{Perc} = P - \text{RO} - \text{ST} - \text{ET}$$

where:

Perc = percolation rate; the portion of precipitation which infiltrates the surface and is not taken up by plants or evaporated

P = precipitation rate

RO = surface water runoff; the portion of the precipitation which does not infiltrate into the ground but instead moves overland away from the site

ST = change in soil moisture storage

ET = Actual evapotranspiration; the combined amount of water returned to the atmosphere through direct evaporation from surfaces and vegetative transpiration.

TABLE 5-1 MAJOR FACTORS AFFECTING LEACHATE GENERATION

Primary Factors	Secondary Factors
Precipitation	quantity, intensity, duration, frequency, seasonal distribution
Liquid Content of Wastes	type, quantity, moisture content, and moisture storage capacity (field capacity)
Liquids from Waste Decomposition	waste composition, waste environment, and micro-organism populations
Groundwater Intrusion	flow rates into pit, seasonal distribution of water table, head levels, liner materials
Soil Moisture Storage	field capacity of materials, seasonal fluctuations
Evapotranspiration	temperature, wind velocity, humidity, vegetation type, solar radiation, soil characteristics
Runon/Runoff Control	diversions, crowning of surface cap, permeability and integrity of cap, depression storage
Operation Mode	open versus closed, coverage
Surface/Cap Conditions	permeability, integrity, surface contour, runoff underdrain systems, subsidence

Values for the parameters needed for such an analysis can be found in a variety of sources or estimated using a variety of techniques. Precipitation values for a given location are available from a number of sources including the National Weather Service. Runoff is very site specific and difficult to measure. Most release rate models use one of the following methods to estimate runoff:

- Rational Formula--utilizes empirical runoff coefficients based on vegetative type, soil type, and slope.
- SCS Curve Numbers--utilizes empirical coefficients which relate runoff to soil type, land use, management practices, and daily rainfall.
- Green-Ampt Equation--approximates runoff based on soil properties, initial water content and distribution, surface conditions, and accumulative infiltration.

Both evapotranspiration and soil moisture storage can be estimated using empirical soil moisture retention relationships such as those developed by Thornthwaite (1955). Some models require that evapotranspiration be a measured site specific input, while others do not specify a method to obtain values. Some models relate evapotranspiration to physical parameters such as temperature, solar radiation, and the leaf area index (LAI), while others store evapotranspiration and soil moisture information for various locations on a national data base that can be accessed by the model. One model also makes simplifying assumptions to estimate soil moisture storage either by apportioning soil moisture into a "wet" zone and a "dry" zone or by using the method of depth-weighted fractional water content within the soil profile.

Release rate models also allow the user to set surface conditions and cover liner characteristics for the site with varying degrees of flexibility. Some methods allow multiple clay-synthetic liners, others only clay liners, while still another can only be applied to open sites

without covers. Cover vegetation, slope, contour, and soil properties can also be specified in all but the most simplistic models.

When cover liners are used to impede percolation to waste cells, excess water moves away from the site through subsurface lateral drainage above the liner. Models estimate this lateral drainage by:

- Approximate methods (utilizing correction factors) derived from the Boussinesq equation for lateral saturated flow.
- Empirical methods development by Moore (1980) which calculate the maximum hydraulic head above the liner and then the upper bound of the quantity of liquid flowing into tile drains. The liner is assumed to be impermeable for these calculations.
- Empirical methods which calculate percolation through the liner and soil moisture storage; then extrapolate lateral drainage as the remaining excess water.

The next step is to predict the flow rate through the top liner. This is ultimately the major contributing factor in leachate generation. Numerous methods are used to predict this percolation rate and they can be divided into methods for clay liners and those for synthetics. Methods used for clay liners include:

- Darcy's Law for saturated conditions, which relates flow velocity to hydraulic conductivity, effective porosity, hydraulic head, and travel distance using the following general equation:

$$V = Kh/nx$$

where: V is flow velocity, K is hydraulic conductivity, n is effective porosity, h is hydraulic head difference, and x is travel distance

- Approximations of saturated Darcy flow as proposed by Wong (1977).
- Soil storage routing techniques through multiple soil layers which relate liner permeability to inflow rate, time interval, hydraulic conductivity, soil water storage, and evapotranspiration.
- Darcy's Law with provisions to arbitrarily increase liner permeability assuming that certain events occur (e.g., burrowing animals or equipment breach of the liner).

- o Prediction of unsaturated flow driven by capillary forces utilizing the Green-Ampt approximation of the wetting front assuming a constant capillary head.

Methods to predict flow through synthetic liners include:

- o Darcy's Law as described above and based on hydraulic head and liner thickness.
- o Power Law relationships for estimating the aging of a liner based on the life expectancy of the liner.
- o Arbitrary methods such as assuming that the liner will be impermeable for 20 years and then will fail completely (i.e., after 20 years the model treats the facility as if it were unlined).
- o Stochastic (Monte Carlo) simulation for liner failure due to aging and installation problems.

The amount of water percolating through the cover liners and into the waste cells is either adjusted according to the moisture content of the wastes and fill materials in the facility, or the wastes and fill materials are assumed to be at field capacity and, therefore, the amount of water percolating into the waste cells is also the total quantity of leachate generated.

Water balances for waste disposal sites produce only relative solutions to leachate generation for comparing different designs or sites. The high degree of uncertainty that exists in these solutions has led to the use of bounding assumptions. Bounding assumptions are based on the knowledge that the quantity of leachate generated at a given facility falls between 0% and 100% of the maximum potential amount (based on total possible leachate), such that upper and lower bounds for leachate generation volume can be established. Using assumptions and empirical data, the bounds can be narrowed to produce best- and worst-case scenarios which can, in turn, be used to design the landfill based upon performance goals.

5.1.1.2 Leachate Constituent Concentrations

For a release rate model to be useful, it must not only estimate the quantity of leachate produced, but it also must estimate the quality (i.e., leachate constituent concentrations). The quantitative simulation of the processes and interactions occurring within a landfill to produce leachate are very complex, and therefore most available models do not attempt to simulate all these processes. Table 5-2 lists some of the factors affecting leachate constituent concentrations that would have to be considered.

Because of the complexity of the interdependent interactions occurring within a disposal site and our inability to accurately characterize these interactions, simulations of the processes are extremely difficult, if not impossible. Consequently, release rate models do not address the factors which govern constituent concentrations. Rather, the models make assumptions to greatly simplify the complexities of the real world. These assumptions are:

- Constituents are at the saturation solubility concentration levels in leachate.
- Constituents exist at equilibrium concentrations between the aqueous and sorbed phases.
- Bounding assumptions are used in a similar manner as described for leachate generation.

5.1.1.3 Leachate Release

Leachate release is defined as the escape of any contaminants beyond the containment boundary of a land disposal facility. The type and magnitude of release depends upon the presence of a liner system, the type of liner employed, the presence and efficiency of a leachate collection system, and the occurrence and magnitude of any system failures. Table 5-3 lists some of the factors affecting leachate release from a land disposal site.

TABLE 5-2 FACTORS AFFECTING LEACHATE CONSTITUENT CONCENTRATIONS

Major Components	Primary Factors	Secondary Factors
Waste Composition	Volume Constituents Constituent Concentrations	
Physicochemical Properties	Solubility Mobility Persistence Volatilization Phase/State	pH; temperature; composition of liquid phase Viscosity; temperature; density; sorption; complexation pH; temperature; presence of catalysts; chemical degradation (e.g. oxidation, reduction, hydrolysis, photolysis); biological degradation Fugacity; constituent vapor pressure; temperature Temperature; pressure
Contact Time	Conditions of Waste Environment	Flow rates through wastes, fill materials and drain layers; waste permeability; waste porosity; particle size; site heterogeneities; capillary action; piping through wastes; ponding in waste cells; plugging of pore spaces
Chemical Reactions and Interactions	Hydrolysis Oxidation	pH; temperature; soil pH, catalysts Presence and type of oxidants; catalysts; oxygen concentration; pH; temperature
Chemical Reactions and Interactions (continued)	Reduction Photolysis Microbial Degradation	Oxygen concentration; complexation state; concentration and type of reducing agents; pH; temperature Solar radiation; transmissivity of water; presence of sensitizers and quenchers Microbial population; soil moisture content; temperature; pH, oxygen concentration, redox potential
Facility Age	Microbial Acclimation Changes in Waste Environment	pH; temperature; removal of most soluble constituents

TABLE 5-3 FACTORS AFFECTING LEACHATE RELEASE

Major Components	Primary Factors	Secondary Factors
Synthetic Liners	Physical Factors	Aging; human activities; internal loading stresses; hydrogeology; bathtub effect; weather resistance; deep root growth, burrowing animals; installation and design problems (e.g., subsidence from improper siting, improperly prepared seams); uplifting by gasses or liquids under pressure; impingment rate; temperature
	Chemical Factors	Chemical disintegration; weather, ultraviolet radiation, chemical and microbial attack from the soil atmosphere; waste-linear compatability; nature soil chemistry; pH, temperature
	Leachate Collection	Efficiency, maintenance; design
Clay Liners	Physicochemical Factors	Chemical dehydration, flocculation/dispersion, alteration of shrink/swell properties; soil piping; leachate characteristics; pore size distribution
	Chemical Factors	Dissolution of chemical species, adsorption properties; chemical disintegration, native soil chemistry
	Physical Factors	Internal loading stresses; dehydration; hydrogeology; weathering; erosion; bathtub effect; aging; impingment rate; hydraulic head; structural and design considerations (e.g., proper siting and design to handle differential subsidence
	Biological Factors	Microbial population; burrowing animals; deep root growth, human activities
	Leachate Collection	Efficiency; maintenance; design

Prediction of leachate releases involves the estimation of leachate quantity escaping from the site over time, which is combined with constituent concentration. The major drawbacks in predicting releases are obtaining realistic estimates of liner lifetime, estimating the probability of liner failure, and establishing cause and magnitude of failure if it occurs. The methods employed to predict releases parallel those used to estimate flow rates through cover liners (described previously as part of the water balance approach).

5.1.2 Selected Release Rate Models

Five release rate models and one series of simple calculations chosen for their potential applicability to Wisconsin zone of saturation landfills are discussed below and summarized in Table 5-4.

DRAINMOD (1980) is a computer model developed to predict the response of water in both the unsaturated and the saturated zones to rainfall, evapotranspiration, specified levels of surface and subsurface drainage, and the use of water table control or subirrigation practices. DRAINFIL (1982) is an adaptation of DRAINMOD for landfills which considers drainage from a sloping layer underlain by a tight clay liner and seepage through the cap. DRAINFIL can also quantify drainage to the leachate collection system and through the underlying clay liner during the time the landfill is open. A water balance for the soil water profile is used to calculate the infiltration rate, vertical and lateral drainage, evapotranspiration, and distribution of soil water in the soil profile using approximate solutions to nonlinear differential equations. The prohibitive cost of using numerical methods to finding solutions to equations of this sort requires that approximate methods be used. Checks of solutions obtained through these methods suggest, however, that satisfactory results can be consistently obtained.

The minimum data required for these models include precipitation (amount, distribution, intensity, and duration), water table elevation, daily potential evapotranspiration (PET), net solar radiation, temperature, humidity, wind velocity, soil moisture content, soil profile

TABLE 5-4

RELEASE RATE MODELS

<u>MODEL</u>	<u>ADVANTAGES</u>	<u>DISADVANTAGES</u>	<u>REFERENCE</u>
DRAINMOD/ DRAINFIL	Predicts response of water in unsaturated zones to rainfall	High cost	Skaggs (1982)
HELP/ HSSWDS	Requires minimum amount of data. Estimates vertical and lateral percolation.	Ignores rainfall intensity, duration, and distribution. Accuracy is questionable	Perrier and Gibson (1980)
LSIPE	Evaluation efficiency of liner design in controlling leachate release.	Estimates release in a single modular waste cell. Based on assumptions of good engineering design (rare in older landfills)	Moore (1980)
PCLTF	Addresses all necessary to predict a mass load release.	Unsaturated zone	U.S. EPA (1982)
LTTM	Accounts for moisture content of wastes and fill material. Includes both gravitational and capillary forces. Simple and easy to use.	Currently being developed. All elements have not been tested.	Pope-Reid Assoc. (1982) (Unpub.)
Release Rate Computa- tions	A series of simple calculations	Some assumptions are questionable.	SCS Engineers (1982)

depth, surface compaction, vegetation, depth of root zone, hydraulic conductivity (saturated and unsaturated), and pressure head. Most of the data are readily available, though some difficulty may exist in obtaining reliable unsaturated hydraulic conductivity and pressure head data. In addition, to simplify calculations, the models assume:

- One-dimensional, saturated flow in the bottom liner.
- Infiltration rates for uniform deep soils with constant initial water content expressed in terms of cumulative infiltration alone, regardless of the rate of application.
- Drainage is limited by the rate of soil water movement to the lateral drains and not by the hydraulic capacity of the drain tubes or outlet.

DRAINMOD is currently being used in assessing agricultural drainage systems and has been field-verified in a variety of locations. DRAINFIL, however, has not yet undergone the final changes needed for its use in assessing infiltration at waste disposal sites, and therefore remains untested.

These models are similar to other release rate models in that they use a water balance approach, do not consider leachate constituent concentrations, and do not consider any processes occurring within the waste cell that may affect leachate quantity or quality. Some unique features of DRAINMOD/DRAINFIL are their ability to predict the upward movement of water, and the precision of their hydraulic head estimates.

Hydrologic Evaluation of Landfill Performance (HELP/HSSWDS)
(Perrier and Gibson, 1980)

The hydrologic evaluation of landfill performance (HELP, formerly HSSWDS) is a one-dimensional, deterministic water balance model modified and adapted from the CREAMS (Chemical Runoff and Erosion from Agricultural Management Systems) soil percolation model for use in estimating the amount of water that will move through various landfill covers. This model can simulate daily, monthly, and annual values for runoff, percolation, temperature, soil-water characteristics, and

evapotranspiration with a minimum of data (e.g., precipitation, mean temperature, solar radiation, leaf area index, and characteristics of the cover material). Should data be unavailable, the model provides default values for such parameters as soil-water characteristics, precipitation, mean monthly temperature, solar radiation, vegetative characteristics and climate based on the location of the site. The model is portrayed by its developers as "no more complex than a manual tabulation of moisture balance."

The HELP model ignores rainfall intensity, duration, and distribution and considers only mean rainfall rates, which could somewhat limit the accuracy of the estimates. It also does not evaluate leachate quality. However, it can estimate percolation through up to eight drainage layers including through the waste cell itself, and estimate lateral drainage through any or all of these layers. Some other features of the HELP model include the ability to provide estimates of the impingement rate of leachate entering the bottom liner collection system, predict the seepage rate through a saturated clay liner, and estimate evapotranspiration and runoff using a minimum of data.

The HSSWDS model has been successfully field verified by Gibson and Malone (1982) and many others. Those HSSWDS users contacted for comments and opinions believed that HSSWDS was very useful in comparing sites or cover designs, but that the accuracy or validity of the outputs could not be determined. HELP is currently undergoing refinement and has not yet been tested.

Landfill and Surface Impoundment Performance Evaluation (Moore, 1980)

The Landfill and Surface Impoundment Performance Evaluation (LSIPE) model attempts to determine the adequacy of designs of hazardous waste surface impoundments and landfills in controlling the amount of fluid released to the environment. LSIPE utilizes a series of linearized equations and simplified boundary conditions to evaluate the efficiency of a proposed liner design in terms of:

- Horizontal flow through sand and gravel drain layers.
- Vertical flow through low permeability clay liners.
- Efficiencies of liner-drain layer systems.
- Seepage through the bottom liner.

LSIPE has the advantage of allowing for nonlinear equations and more complex boundary conditions to be employed if needed. Only transport of liquids through a single modular waste cell can be estimated; however, modules can then be arranged in the proposed configuration for analysis. The LSIPE approach also possesses the unique capability of allowing for leachate releases to be measured indirectly through the efficiency of the leachate collection system.

In order to provide estimates of the above mentioned parameters, this approach requires:

- Liquid routing diagram for the site.
- Water balance for the site.
- Slopes in the routing system.
- Hydraulic conductivities.
- Service life of any synthetic liners.

The LSIPE model also makes the general assumption that the operating conditions for a waste landfill or surface impoundment meet the basic requirements of good engineering design, including:

- Surface water runoff has been intercepted and directed away from the site so that only the rainfall impinging directly on the landfill needs to be accounted for.
- Proper precautions have been taken to prevent erosion of the cover soils which would degrade cover performance.
- Synthetic liners have been installed properly to ensure their integrity for design life.

Post-Closure Liability Trust Fund Model (PCLTF) (U.S. EPA 1982)

This model is being developed to assess the adequacy of the Post-Closure Liability Trust Fund established as the result of the passage of CERCLA in 1980. The fund will provide for liability claims resulting from failure of RCRA permitted sites after proper closure. The analytical approach involves:

- Assessing failure probabilities of facilities.
- Determining environmental exposure.
- Assessing damage potential.
- Quantifying damages, and assessing costs for clean-up, remedial action, damage to natural resources, personal injury and economic loss.

PCLTF is the only model reviewed which addresses all three components necessary to predict a mass load release from a land disposal site. The model can be applied to open or closed facilities with both clay and/or synthetic liners. The user can specify one of seven generic site types from a variety of cover and bottom liner and leachate collection configurations. The components of the model consists of:

- User-supplied inputs which characterize the site design and operation, and identify the wastes placed within the fill.
- A data base of physical and chemical characteristics of waste constituents which relate to their solubility, toxicity, persistence, and mobility as well as their effect on synthetic liner performance.
- A data base of climate, soils, and the geology of various regions of the U.S.
- A baseline analysis with which to set initial site conditions.
- Water movement simulation which uses Monte Carlo simulation techniques to generate values for seepage velocity, effective porosity, dispersion, and liner failure to route leachates through the layers of the landfill, including liners and drain layers. Adjustments to leachate quantity are made based on moisture content of wastes and fill materials.

This model's output is a two-dimensional, uniformly distributed, leachate discharge estimate (concentration and flux) to the unsaturated soil column beneath the site. The output provides the source term for a mass transport module for the unsaturated zone.

Leachate Travel Time Model (LTTM) (Pope-Reid Associates, 1982)

The Leachate Travel Time Model (currently under development by Pope-Reid Associates) combines several analytical techniques and previously developed models to evaluate the performance of landfills of various designs in a variety of climatic settings. The model consists of a monthly, quarterly, or annual hydrologic and waste budget which is used to calculate leachate volume in the active fill area, leachate head in drain layers, containment time and seepage rate through the bottom liner, and travel time and seepage rate in the unsaturated zone below the landfill. The model possesses the unique feature of accounting for the moisture content of wastes and fill materials. Actual measured values or estimations of moisture content can be input. Also, the model includes both gravitational and capillary forces to calculate seepage rates through liners.

The Leachate Travel Time Model does not include a specific cover liner option, although the user can incorporate a cover liner by altering the hydrologic budget. Like other models, the current program does not address constituent concentrations of contaminant mass transport, but the authors do intend to incorporate constituent transport in the future. The model does, however, address both leachate generation and release in a relatively simple and easy-to-use program which incorporates many interesting features.

Release Rate Computations for Land Disposal Facilities (SCS Engineers, 1982)

This approach consists of a series of simple calculations to predict the quantity of leachate generated and released from landfills and surface impoundments which will be incorporated into EPA's RCRA Risk/Cost

Policy Model Project (ICF Incorporated, Clement Associates, Inc., and SCS Engineers, Inc., 1982). The approach assumes that:

- Synthetic liners last for 20 years, after which liquid moves freely through them.
- Clay liners retain their integrity for longer than 100 years.
- The only sources of liquids are infiltration from the surface and free liquids in waste. Only saturated flow takes place through the liner in the absence of free liquids.
- Infiltration through the cover system after closure is less than or equal to leachate movement through the liner system.
- Synergistic effects do not occur.

The time required for leakage to appear beneath the bottom of a clay liner is given by:

$$t = Twd^2/4D$$

where:

t = time to first appearance of leakage (sec)

d = thickness of clay liner (cm)

D = linearized diffusivity constant, (cm^2/sec) assumed to be $10^5 \text{ cm}^2/\text{sec}$.

The volume of leachate release over time is given by:

$$q = Ks(dh/d_z)A(\Delta t)$$

where:

q = volume of leachate released over time

Ka = saturated permeability coefficient

dh = hydraulic gradient

dz

A = Area at base of facility

Δt = length of time over which leachate releases.

5.2 Solute Transport Models

Once the quantity and quality of a release from a land disposal site has been determined, this estimate can be used as the input for a solute transport model. Solute transport models predict the migration of chemical constituents away from a source over time in one, two, or three dimensions. A brief discussion of the principles used in transport modeling and descriptions of several transport models are contained in the following sections.

5.2.1 Fundamentals

The transport models presented in this section are all mathematical models, rather than rating or ranking type models (e.g., the MITRE Model). The mathematical approach to modeling involves applying a set of equations, based on explicit assumptions, to describe the physical processes affecting pollutant transport from a site. These models can be divided into two types--deterministic and stochastic. Deterministic models attempt to define the shape and concentration of waste migration using the physical processes (e.g., groundwater flow) involved, while stochastic models attempt to define causes and effects using probabilistic methods. Models presented in this report are generally deterministic.

Deterministic mathematical models can be further divided into analytical models and numerical models. Analytical models simplify mathematical equations, allowing solutions to be obtained by analytical methods (i.e., function of real variables). Numerical models, on the other hand, approximate equations numerically and result in a matrix equation that is usually solved by computer analysis. Both types of deterministic models address a wide range of physical and chemical characteristics but the analytical models usually simplify the characteristics by assuming steady state conditions. The physical and chemical characteristics considered by these models include:

- Boundary Conditions--hydraulic head distribution, recharge and discharge points, locations and types of boundaries.

- Material Constants--hydraulic conductivity, porosity, transmissivity, extent of hydrogeologic units.
- Attenuation Mechanisms--adsorption-desorption, ion exchange, complexing, nuclear decay, ion filtration, gas generation, precipitation-dissolution, biodegradation, chemical degradation.
- Hydrodynamic Dispersion--diffusion and dispersion (transverse and longitudinal).
- Waste Constituent Concentration--initial and background concentrations, boundary conditions.

Both mathematical model types incorporate two sets of equations to define transport; a groundwater flow equation and a mass transport equation. Figure 5-1 illustrates the relationship between these equations.

A general form of the water momentum balance equation for nonhomogeneous anisotropic aquifers (Pope-Reid Associates (1982)) is:

$$\frac{\partial}{\partial x_i} (K_{ij} \frac{\partial h}{\partial x_j}) = S \frac{\partial h}{\partial t} + W$$

where:

h = hydraulic head

K = hydraulic conductivity

S = storage coefficient

W = volume flux per unit area (e.g., pumping or injection wells, infiltration, leakage)

x = distance

t = time

The Darcy equation is generally represented as:

$$V_i = \frac{-K_{ij}}{n} \left(\frac{\partial h}{\partial x_j} \right)$$

where:

V = groundwater velocity

n = porosity

K = hydraulic conductivity




Figure 5-1. Major Components of Groundwater Transport Equation
(after Mercer and Faust, 1981)

The mass transport side of the model, which describes the concentrations of a chemical species in a flow pattern in general form is:

$$\frac{\partial c}{\partial t} = \frac{\partial}{\partial x_i} (D_{ij} \cdot \frac{\partial C}{\partial x_j}) - \frac{\partial}{\partial x_i} (CV_i) - \frac{C'W}{n} + R$$

where:

C' = concentration of solute in the source or sink fluid

C = chemical species concentration

D = dispersion tensor (i.e., hydrodynamic dispersion)

V = groundwater velocity (i.e., convection transport)

R = rate of chemical species attenuation/transformation

These equations are coupled to provide predictions of solute transport in the groundwater system with chemical reactions considered. For analytical models, these equations are simplified to explicit expression. For either type of model, a sensitivity analysis of model results can be performed by varying the input characteristics singularly or in combination. One type of sensitivity analysis that could be performed involves changing single parameters (within known values of occurrence) to demonstrate the effects that variations in individual parameters have on model output. This analysis helps identify those parameters which have the greatest influence on model results. A second type of sensitivity analysis involves a series of trial runs of the model using an array of input parameters which vary in accordance with the expected errors associated with each parameter (i.e., Monte Carlo simulation techniques). This method provides a general assessment of the overall model sensitivity and intrinsic precision by providing a range of variations of the model outputs as a function of the error bars associated with the input parameters (e.g., mean values, maximum values, minimum values).

5.2.1.1 Analytical Models

Analytical models provide estimates of waste constituent concentrations and distributions using simplified, explicit expressions

generated from partial differential equations. The mathematical expressions are usually simplified by assuming steady state conditions relative to fluid velocity, dispersion dynamics, and other physical parameters. For example, groundwater flow equations can be simplified if the aquifer is assumed to have infinite extent. Governing equations characterize both groundwater flow and mass transport, and may also address dilution, dispersion, and attenuation. These models can simulate plume migration from the source to a utilized groundwater system allowing for attenuation and dispersion. The method provides a quick and inexpensive solution with minimal amounts of data as long as the simplifying assumptions do not render results invalid.

5.2.1.2 Numerical Models

Numerical models characterize groundwater contamination processes without the simplification of complex physical and chemical characteristics required by analytical models. The numerical models reduce the partial differential equations to a set of algebraic equations that define hydraulic head at specific points (i.e., grid points). These equations are solved through linear algebra using matrix techniques.

The numerical methods most commonly used to simulate groundwater transport problems can be divided into four groups: finite difference (FD); finite element (FE); method of characteristics (MOC); and discrete parcel random-walk (DPRW). In each method, the governing equations (e.g., groundwater flow equations) are solved by subdividing the entire problem domain into a grid system of polygons. Every block has assigned hydrogeologic properties (e.g., transmissivity) associated with it that define the aquifer. Accompanying each grid is a node point that represents the position of an equation with unknown values (e.g., head). For the finite difference method, the derivatives of the partial differential equations are approximated by linear interpolation (i.e., the differential approach). In the finite element method the partial differential equations are transformed to integral form (functionals) and minimized to solve the dependent variables. The algebraic equations for each node point, derived by the FD or FE methods, are then combined to

form a matrix equation which is solved numerically. The FE method is better suited for solving complex two- and three-dimensional boundary conditions than the FD method. When using FD or FE methods for solving contaminant transport problems, results are subject to numerical dispersion or numerical oscillation. Numerical dispersion causes answers to be obscured because of accumulated round-off error at alternating time steps. Numerical oscillation causes answers to overshoot and undershoot the actual solution at alternating time steps. Numerical oscillation is generally associated with FE methods, while numerical dispersion is generally associated with FD methods.

The method of characteristics and discrete parcel random-walk models were developed to minimize the numerical difficulties associated with the FE and FD methods. Both the method of characteristics (MOC) and discrete parcel random walk method analyze temporal changes in concentrations by tracking a set of reference points that flow with the groundwater past a fixed grid point. In the MOC method, points are placed in each finite difference block and allowed to move in proportion to the groundwater velocity at the point and the time increment. Concentrations are recalculated using summed particle concentrations at the new locations. The random-walk method varies from the MOC method because, instead of solving the transport equation, a random process defines dispersion. Reference points move as a function of groundwater flow, consistent with a probability function related to groundwater velocity and dispersion (longitudinal and transverse). The methods provide comparable results but the MOC method is time consuming, expensive, and requires considerable computer storage.

5.2.2 Selected Solute Transport Models

Eight analytical models and nine numerical models are presented in the following sections. Each has characteristics that make it unique; therefore, selection of a model should be based on making the best use of available data given the desired output. These models are summarized in Table 5-5.

TABLE 5-5 SOLUTE TRANSPORT MODELS

<u>MODEL</u>	<u>ADVANTAGES</u>	<u>DISADVANTAGES</u>	<u>REFERENCE</u>
(Analytical)			
SESOIL	"User-friendly", addresses numerous processes.	Field and analytical verifications not yet performed. Designed for un-saturated zone simulations.	Bonazountas and Wagner (1981)
PESTAN	Calculates pollutant velocity, length of pollutant slug, contaminant concentrations. Easy to use, inexpensive, can be used as a screening model. Can be coupled with PLUME.	One dimensional through un-saturated zone.	Enfield, et al., (1982)
PLUME	A saturated zone model. Provides 2-dimensional plume traces.	Effects of adsorption and degradation ignored in testing.	Wagner (1982)
Leachate Plume Migration Model	Predicts plume migration and mixing in saturated zone. Methods of use are simplified.		Kent, et al., (1982)
Cleary Model	10 different models using a variety of boundary conditions. Little information available.		Cleary (1982)

TABLE 5-5 SOLUTE TRANSPORT MODELS (Continued)

<u>MODEL</u>	<u>ADVANTAGES</u>	<u>DISADVANTAGES</u>	<u>REFERENCE</u>
(Analytical)			
AT123D	Estimates waste transport in saturated and unsaturated zones. Computer coded, available, valuable for preliminary assessments.	Appears to have not been field verified.	Yeh (1981)
Screening Procedure	Assesses transport and degradation in saturated zone of specific chemicals. Provides quantitative and qualitative screening based on estimates of exposure.	Does not address synergistic effects. Unpublished and not available to public.	Falco, et. al. (1980)
PATHS	Used for saturated flow. Estimates single contaminant transport. Fast, inexpensive.	Ignores dispersion effects. Has not been field verified	Nelson and Sheen (1980)
(Numerical Models)			
MMT/VTT/ UNSAT I D	Used for saturated or unsaturated zone. Computer package available for graphic displays.	As with all numerical models, costs are high as are requirements for accurate geohydrologic data.	Battelle (1982)

TABLE 5-5 SOLUTE TRANSPORT MODELS (Continued)

<u>MODEL</u>	<u>ADVANTAGES</u>	<u>DISADVANTAGES</u>	<u>REFERENCE</u>
(Numerical Models)			
CFEST/ UNSAT ID	CFEST predicts fluid pressure, temperature, and contaminant concentrations in saturated zone.	Presently being field verified. Model documentation in preparation.	Battelle (1982)
Pollutant Movement Simulator	Three-dimensional model for coupled saturated-unsaturated zone.	Has not been tested for landfills.	Khaleel and Reddell,
FEMWASTE	Two-dimensional model for coupled saturated-unsaturated zones. Utilizes FEMWATER.		Yeh (1981)
Random Walk Solute Transport Model	Saturated zone model. Concentrations can be specified in any segment of model. Documented, available to public, and verified.		Prickett, et al., (1981)
SWIFP	Saturated zone models three-dimensional. Field and analytically verified, well documented.		USGS (1982)
Solute Transport/ Groundwater Flow Model	Saturated zone. Analytically and field verified.	Ignores dispersion.	Golder Associates (1982)
Leachate Organic Migration and Attenuation Model	Coupled saturated-unsaturated zones. Specifically designed for landfills.	Currently being revised.	Sykes, et al. (1982)

5.2.2.1 Analytical Models

The eight analytical models characterized in this section do not address cases involving secondary porosity, immiscible liquids, or more than one contaminant. Only one model, AT123D developed by G.T. Yeh (1981), considers both the saturated and unsaturated hydrologic zones; the other models are restricted to modeling only one hydrologic zone.

SESOIL (Bonazountas and Wagner, 1981)

SESOIL, a seasonal soil compartment model, was developed by A.D. Little Inc. for the U.S. EPA Office of Toxic Substances. The model is described as a "user-friendly" statistical/analytical mathematical model designed for long term environmental pollutant fate simulates. Simulations are performed for the unsaturated zone and are based on a three-cycle rationale--the water cycle, the sediment cycle, and the pollutant cycle. SESOIL addresses numerous processes including diffusion, sorption, chemical degradation, biological degradation, and the complexation of metals. The model is presently being updated and is available for limited use although field or analytical verifications have not yet been performed.

PESTAN (Enfield, et al., 1982)

PESTAN was developed at the EPA Robert S. Kerr Environmental Research Laboratory. The model calculates the movement of organic substances in one dimension through the unsaturated zone based on linear sorption and first order degradation (i.e., hydrolysis and biodegradation). Calculated outputs include pollutant velocity, length of the pollutant slug, and contaminant concentrations. Pollutant application rates to the soil surface can be changed to determine the effect of the number of applications, application period, and number of days before reapplication. This model is best classified as a screening model because it provides for a rapid evaluation of chemicals without the sophistication of numerical models. The model is also easy to use and inexpensive. PESTAN can be coupled with PLUME, a saturated zone analytical model. PESTAN has been field verified for the chemicals DDT and Aldicarb, and the model is being used by EPA-Athens.

PLUME (Wagner, 1982)

PLUME is a steady state analytical model developed at Oklahoma State University to model contaminant transport in the saturated zone. The model provides two-dimensional plume traces from a continuous source and allows for first order degradation and linear sorption (i.e., organic pollutants) with dispersion. The model was verified using a case history of groundwater contaminated with hexavalent chromium, although the effects of adsorption and degradation were ignored.

Leachate Plume Migration Model (Kent, et. al. 1982)

The Leachate Plume Migration Model was developed as an analytical technique for the hazard evaluation of existing and potential, continuous source waste disposal sites by predicting plume migration and mixing in the saturated zone. Predictions can be made from nomographs, hand-held calculators, or a large scale computer. The model allows for degradation (i.e., radioactive and biological) of constituents and for the effects of dispersion and diffusion. The predictive methods presented are simplified so that a strong background in mathematics and computer programming are not required for their use. The model has been verified using data from a chromium plume at Long Island and is presently being tested against other case studies.

Cleary Model (Cleary, 1982)

The Cleary Model consists of ten different analytical models that describe mass transport and groundwater flow, with dispersion, under a variety of boundary conditions. The model addresses conservative constituents (i.e., without degradation). The ten available models are:

- 1-dimensional, mass transport; 1st type boundary conditions.
- 1-dimensional, mass transport; 3rd type boundary conditions.
- 2-dimensional, mass transport; strip boundary, finite width.
- 2-dimensional, mass transport; strip boundary, infinite width.
- 2-dimensional, mass transport; Gaussian source, infinite width.

- 3-dimensional, mass transport; patch source, finite dimensions.
- 3-dimensional, mass transport; 5 area Gaussian source.
- 2-dimensional, groundwater flow; infinite dimensions, recharge boundary.
- 2-dimensional, groundwater flow; finite dimensions, recharge boundary.
- 2-dimensional, groundwater flow; infinite dimensions, no recharge.

These models were not available for review and R. Cleary (developer) could not be contacted; information concerning these models was, therefore, very limited.

AT123D (Yeh, 1981)

AT123D, developed by G. T. Yeh at Oak Ridge National Laboratory, is a generalized transient, one-, two-, or three-dimensional analytical computer model for estimating waste transport in both the unsaturated and saturated zones. The model is flexible, providing 450 options: 288 for the 3-dimensional case; 72 for the 2-dimensional case in the x-z plane; 72 for the 2-dimensional case in the x-y plane; and 18 for the 1-dimensional case in the longitudinal direction. AT123D models all of the following options:

- Eight sets of source configurations (i.e., point source; line source parallel to x-, y-, or z-axis; area source perpendicular to the x-, y-, or z-axis; and a volume source).
- Three kinds of source releases (instantaneous, continuous, and finite duration releases).
- Four variations of the aquifer dimensions (finite depth and width, finite depth and infinite width, infinite depth and finite width, infinite depth and infinite width).
- Modeling of radioactive wastes, chemicals, and head levels.

The transport mechanisms addressed are advection, hydrodynamic dispersion, adsorption, decay/degradation, and waste losses to the atmosphere from the unsaturated zone. The model is computer coded and publicly available, making it a potentially valuable tool for preliminary assessment of waste disposal sites. Fifty sample problems (simulations) have been performed but actual field verification appears to be lacking.

Screening Procedure (Falco et al., 1980)

A screening procedure for assessing the transport and degradation of solid waste constituents in the saturated zone as well as surface waters was developed by Falco et al., (1980). The procedure estimates the movement and degradation of chemicals released from landfills and lagoons based on the physical and chemical properties of the compound and a defined range of environmental conditions that the compound would be expected to encounter in groundwater. The procedure developed involves two parts, a mathematical model to obtain quantitative estimates of exposure and a logic sequence that assigns qualitative descriptors of behavior (e.g., low, significant, high) based on the quantitative estimates of exposure. Quantitative estimates are based on hydrolysis, biological degradation, oxidation, and sorption. The results of using this procedure indicate that it provides a means of qualitatively screening organic chemicals when specific process rates are available.

PATHS (Nelson and Schur, 1980)

The PATHS groundwater model is a hybrid analytical/numerical model for two-dimensional, saturated groundwater flow that estimates single contaminant transport under homogeneous geologic conditions. The model also considers the effect of equilibrium ion exchange reactions for a single contaminant at trace ion concentrations. Dispersion effects are not considered by the model. The model provides a fast, inexpensive, first-cut evaluation consistent with the amount of field data usually available for a site. Analytical verifications have been performed but field verifications have not.

5.2.2.2 Numerical Models

The nine numerical models characterized in this section generally address the following characteristics:

- Coupled saturated/unsaturated zones.
- Primary porosity.
- Heterogeneous, anisotropic aquifers.
- Miscible constituents.
- Dispersion.
- Attenuation/degradation.

This group of models represents the most flexible approach to modeling a wide range of hydrogeologic conditions and contaminant types because the governing equations are not simplified as they are for the analytical models. These models generally involve greater costs and require accurate geohydrologic data for a given site.

MMT/VTT/UNSAT1D (Battelle, 1982)

MMT (Multicomponent Mass Transport) is a one- or two-dimensional mass transport code for predicting the movement of contaminants in the saturated or unsaturated zone. The MMT model utilizes the discrete parcel random-walk method and was originally developed to simulate the migration of radioactive contaminants. The model accounts for equilibrium sorption, first-order decay and n-members radioactive decay chains. A velocity field (i.e., groundwater flow equations) must be input to the model and this is generally accomplished by coupling with the VTT (Variable Thickness Transient) model for the saturated zone and UNSAT1D (One-Dimensional Unsaturated Flow) model for the unsaturated zone. A computer package facilitates interpretation of results by providing graphic data displays. The model has been used at the Hanford, Washington, site to predict tritium concentrations.

CFEST/UNSAT1D (Battelle, 1982)

CFEST (Coupled Fluid Energy and Solute Transport) predicts fluid pressure, temperature, and contaminant concentrations in saturated groundwater systems. Coupling the model with UNSAT1D allows for modeling the unsaturated zone. The model applies finite element techniques to solve equations. The flow system may be complex, multi-layered, heterogeneous and anisotropic with time-varying boundary conditions and time-varying areal sources and sinks. Sorption and contaminant degradation are presently being incorporated into the model. The model is presently being field verified for EPA at the Charles City, Iowa, site for arsenic and pharmaceutical chemical waste (organics). Model documentation is in preparation.

Pollutant Movement Simulator (Khaleel and Reddell, 1977)

The Pollutant Movement Simulator is a three dimensional model describing the two-phase (air-water) fluid flow equations in a coupled saturated-unsaturated porous medium. Flow equations are solved by finite difference methods. A three dimensional convective-dispersive equation was also developed to describe the movement of a conservative, noninteracting tracer in nonhomogeneous, anisotropic porous medium. Convective-dispersive equations are solved by the method of characteristics. Attenuation processes have been incorporated into the model since its original release. The model has been tested for salt (NaCl) movement in sample plots and is presently being used in coal mine contamination studies.

FEMWASTE (Yeh, 1981)

FEMWASTE, developed by G. T. Yeh at Oak Ridge National Laboratory, is a two dimensional, finite element, mass transport model for the coupled saturated-unsaturated hydrologic zones. This model utilizes FEMWATER, also developed by Yeh, to provide the groundwater flow field allowing for a variety of boundary conditions and initial moisture conditions.

Additionally, FEMWASTE incorporates the effects of convection, dispersion, chemical sorption and first order decay in the mass transport equations. FEMWASTE/FEMWATER is computer coded and available to the public. This model has been field verified and is presently being used by the Carson City office of the USGS.

Random Walk Solute Transport Model (Prickett et al., 1981)

The Random Walk Solute Transport Model, developed by Prickett, Naymik, and Lonquist (1981), predicts the transport of chemical species (e.g., organics, metals, inorganics) in the saturated zone by the random walk or particle-in-a-cell method. Mass transport equations include provisions for dispersion and chemical reactions (attenuation). The model also accounts for time varying pumpage, injection by wells, natural or artificial recharge, water exchange between surface water and groundwater, and flow from springs. Chemical constituent concentrations in any segment of the model can be specified. Flow equations are solved by finite difference methods. The model has been documented and made available to the public. Analytical and field (i.e., fertilizer plant, Meredosia, Illinois) verifications have been performed.

Solute Transport and Dispersion Model (Konikow and Bredehoeft, 1974)

The Solute Transport and Dispersion Model simulates the movement of conservative chemical species in a two dimensional, coupled unsaturated-saturated hydrologic zone. Flow equations are solved using the finite difference method while mass transport equations are solved by the method of characteristics. The model allows for the incorporation of pumping or recharging wells, diffuse infiltration, and for varying the transmissivity, boundary conditions, contaminant concentrations, and saturated thickness. Analytical and numerous field verifications have been performed for the model (e.g., Hanford Reservation, Washington for radioactives; Rocky Mountain Arsenal, Colorado for pond leachate).

SWIFP (USGS, 1978)

The SWIFP model simulates the movement of nonconservative constituents through the saturated zone in three dimensions. The model incorporates dispersion processes and also allows for deep well injection predictions. Flow and transport equations are solved by the finite difference method. This model is well documented and maintained, and has been field and analytically verified. Presently field verifications are being performed in New Jersey for sea-water intrusion, in Carson City for geothermal transport, and in Minnesota for coal tar residues. A version of SWIFP has also been developed for the Nuclear Regulatory Commission to handle radioactive materials.

Solute Transport/Groundwater Flow Model (Golder Associates, 1982)

This model simulates the movement of multiple conservative constituents without dispersion in the saturated zone. Flow and mass transport equations are solved using finite element techniques. The model has been analytically and field verified.

Leachate Organic Migration and Attenuation Model (Sykes et al., 1982)

The Leachate Organic Migration and Attenuation Model simulates the movement of nonconservative organic solutes through the saturated-unsaturated zone. The model is generally run in one or two dimensions but can be modified for three dimensional analysis. Flow and mass transport equations are solved by finite element techniques. This model is specific to sanitary landfills because it measures organics as chemical oxidation demand, and addresses biodegradation, adsorption, convection, and dispersion processes. The model is currently being revised. Field verification has been performed for the model at the Borden Landfill, Ontario, Canada for chloride and potassium, at granite sites for nuclear wastes, and for aldicarb.

5.3 Model Limitations

The following issues provide a context for considering the limitations inherent in the application of models to evaluate or predict groundwater problems.

- Modeling results represent approximations of the actual movement of contaminants and groundwater; results should be used to estimate the comparative magnitude of a problem and to assign priorities.
- Models should be verified against actual field observations to determine how closely they simulate real world situations; verification should be performed in the actual hydrogeologic system to which the model is to be applied.
- Model accuracy may vary dramatically when models are applied to situations for which they have not been verified.
- Models presently do not simulate all the processes that control contaminant movement; the equations that describe attenuation and dispersion are especially weak in most models.
- Generally, the capacity of a model to simulate field situations is a function of its complexity; the more complex the model, the more data are required. Model reliability becomes a function of data accuracy, i.e., "garbage in, garbage out".
- Models for which sensitivity analyses have not been conducted may generate mathematical errors when parameters are changed and assumptions modified.

Because of the complexity and limitations of models, assertions determined through the use of models should not be interpreted as actual values but only as estimates.

For Wisconsin zone of saturation landfills, those models which address leachate production, such as DRAINMOD/DRAINFIL and LSIPE, are applicable. LTTM may be useful when fully documented and verified. Solute transport models, such as SWIFP and the Random Walk Solute Transport Model, may be applicable if leachate migration from existing landfills is detected or suspected.

6.0 RECOMMENDATIONS

Zone of saturation landfills are by nature very susceptible to contaminant releases because of the large amounts of water, both groundwater inflows and leachate, that must be removed by the drainage system. If the only sites available for construction of the landfills are in the saturated zone, the following recommendations may help limit the probabilities of leachate release:

- Determine as accurately as possible the values of inflow rates (q) and hydraulic conductivities (K) of both landfill material and soils because these values have a major impact on drain system design, especially drain spacing.
- Determine the hydrogeology of the site accurately so that groundwater level variations throughout the year are known and conservative head maintenance levels can be specified (i.e., always maintaining inward hydraulic gradients).
- Design the landfill base so that it slopes toward the drains, thus allowing for lower head maintenance levels and more rapid leachate removal.
- Specify low head maintenance levels within the fill, thus reducing the hydraulic head capable of discharging leachate (i.e., for hazardous waste sites, EPA regulations require heads less than 1-foot).
- Select the proper drain equation for system design and allow for a margin of error in the results obtained (i.e., design conservatively).
- Design filters and envelopes for drain pipes that prevent silting and allow for free flow of liquids.
- Remove daily fill covers from cells or ensure by some other means that the cells are hydraulically connected to the drainage system thus allowing free flow of water between cells and drains.

- Incorporate drain blankets into landfill designs to reduce head maintenance levels without decreasing drain spacing and improve the overall efficiency of leachate collection.
- Compact clay base and sidewall layers at optimum working moisture conditions so that high density, low permeability barriers are created without shearing or fracturing the clay.
- Provide construction inspections to ensure that critical operations such as placement of leachate collection drain and filter envelopes, base gradings, and clay recompaction are performed as specified.
- Design leachate collection system so that routine maintenance and inspections can be performed to adequately maintain flows.
- Provide for continuous monitoring of leachate collection volumes and head levels so that problems can be identified quickly.
- Design landfill drainage systems to incorporate anticipated future operations such as the acceptance of large quantities of liquids.

Understanding the drain equations and the theory behind them and incorporating the above recommendations into the original landfill design can substantially reduce the chances of leachate release. However, unless the designs are incorporated properly during construction, the system will fail to meet its intended purpose.

7.0 BIBLIOGRAPHY

7.1 Background

Fenn, D.G., K.J. Hanley, and T.V. Degeare. 1975. Use of the water balance method for predicting leachate generation from solid waste disposal sites. U.S.EPA-530/SW-168, Cincinnati, Ohio. 40 pp..

Fungaroli, A.A. 1971. Pollution of subsurface water by sanitary landfills. U.S.E.P.A. Solid Waste Management Series, SW-12rg. Vol. 1. 132 pp.

Fungaroli, A.A. and R.L. Steiner. 1979. Investigation of sanitary landfill behavior. Volume 1. U.S.E.P.A. 600/2-79-053a.

Gerhart, R.A. 1977. Leachate attenuation in the unsaturated zone beneath three sanitary landfills in Wisconsin. University of Wisconsin - Wisconsin Geological and Natural History Survey. Info. Circular No. 3. 93 pp.

Green, J.H. et al. 1965. Groundwater pumpage and water level changes in Milwaukee-Waukesha area, 1950-61. USGS Water Supply Paper 1809-I.

Harr, C.A., L.C. Trotta, and R.G. Borman. 1978. Ground-water resources and geology of Columbia County, Wisconsin. University of Wisconsin - Extension. Geological and Natural History Survey. Info. Circular No. 37. 30 pp.

Holt, C.L.R., Jr. 1965. Geology and water resources of Portage County, Wisconsin. USGS Water Supply Paper 1796. 77 pp.

Hughes, G.M. et al. 1971. Hydrogeology of solid waste disposal sites in Northeastern Illinois. U.S.E.P.A. Publication No. SW-12d. 154 pp.

LeRoux, E.F. 1957. Geology and ground water resources of Outagamie County. USGS Water Supply Paper 1604.

Newport, T.G. 1962. Geology and ground water resources of Fond du Lac County, Wisconsin, USGS Water Supply Paper 1604.

Olcott, P.G. 1966. Geology and water resources of Winnebago County, Wisconsin. Geological Survey Water Supply Paper 1814.

Roudkivi, A.J. and R.A. Callander. Analysis of groundwater flow. John Wiley and Sons, N.Y. 214 pp.

Sherrill, M.G. 1978. Geology and ground water in Door County, Wisconsin, with emphasis on contamination potential in the Silurian Dolomite. Geological Survey Water Supply Paper 2047.

Soil Conservation Service. 1980. Ground water resources and geology of Washington and Ozaukee Counties, Wisconsin. University of Wisconsin - Extension. Geological and Natural History Survey. Inform Circular No. 38, 37 pp.

Young, H.L. and Batten, W.G. 1980. Soil Survey of Winnebago County, Wisconsin. U.S. Department of Agriculture.

7.2 Drains

Bureau of Reclamation. 1978. Drainage Manual. Water Resource Technical Publication. United States Government Printing Office, Washington, D.C. 286 pp.

DuPont Company. 1981. Designing and Constructing Subsurface Drains. DuPont Company, TYPAR Sales, Wilmington, Delaware.

Hooghoudt, S.B. 1940. Bijdragen tot de kennis van enige natuurkundige grootheden van de grond. No. 7. Versl. Landbouwk. 46:515-707.

Konet, P., K.J. Quinn and C. Slavik. 1981. Analysis of design parameters affecting the collection efficiency of clay lined landfills. In: Proceedings of Fourth Annual Madison Conference of Applied Research and Practice on Municipal and Industrial Waste. September 28-30, University of Wisconsin Extension, Madison, WI.

Moore, C.A. 1980. Landfill and Surface Impoundment Performance Evaluation. U.S. Environmental Protection Agency, SW-869, Office of Water and Waste Management, Washington, D.C.

Moulton, L.K. 1979. Design of subsurface drainage systems for the control of groundwater. Presented at: 58th Annual Presentation of the Transportation Research Board, Washington, D.C.

Powers, J.P. 1981. Construction Dewatering. John Wiley and Sons. New York. 484 pp.

Sichardt, W. and W. Kyrieleis. 1940. Grundwasserabenkungen bei Fundierungsarbeiten. Berlin, Germany.

Soil Conservation Service. 1973. Drainage of Agricultural Land. Water Information Center, Inc. Syosset, New York. 430 pp.

Van Schlifgaarde, J. 1974. Drainage for Agriculture. American Society of Agronomy 17, Madison, Wisconsin.

Wesseling, J. 1973. Theories of Field Drainage and Watershed Runoff: Subsurface Flow into Drains. In: Drainage Principles and Applications, International Institute for Land Reclamation and Improvement. P.O. Box 45, Wageningen, The Netherlands.

Winger, R.J. and W.F. Ryan. 1970. Gravel Envelopes for Pipe Drain-Design. American Society of Agricultural Engineers. Chicago, Illinois, December 8-11.

7.3 Flow Nets

Bennett, R.R. 1962. Flow Net Analysis. In: Ferris, J.G., D.B. Knowles, R.M. Brown, and R.W. Stallman. 1962. Theory of Aquifer Tests: U.S. Geological Survey Water Supply Paper 1536-E, pp. 139-144.

Bennett, R.R., and R.R. Meyer. 1952. Geology and Groundwater Resources of the Baltimore Area. Maryland Department of Geology, Mines, and Water Resources. Bulletin 4, 573 p.

Cedergren, H.E. 1977. Seepage, Drainage, and Flow Nets (2nd Edition). John Wiley and Sons, New York. 534 p.

Freeze, R.A. and J.A. Cherry. 1979. Ground Water. Prentice-Hall, Englewood Cliffs, New Jersey. pp. 168-191.

Lohman, S.W. 1979. Ground Water Hydraulics. U.S. Geological Survey Professional Paper 708. 70 p.

Mansur, C.I. and R.I. Kaufman. 1962. Dewatering. In: Leonards, G.A. (Ed.). 1962. Foundation Engineering. McGraw-Hill, New York. pp. 241-350.

Powers, J.P. 1981. Construction Dewatering - A Guide to Theory and Practice. John Wiley and Sons, New York. 484 pp.

7.4 Models

7.4.1 Release Rate Models

Ali, E.M., C.A. Moore, and I.L. Lee. 1982. Statistical Analysis of Uncertainties of Flow of Liquids Through Landfills. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 26-52.

Anderson, D., K.W. Brown and T. Green. 1982. Effect of Organic Fluids on the Permeability of Clay Soil Liners. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 174-178.

Bailey, G. November 1982. Personal communication.

Barrier, R.M. 1978. Zeolites and Clay Minerals as Sorbents and Molecular Sieves. Academic Press, New York. 497 pp. As cited in Haxo et al., 1980.

Brady, N.C. 1974. The Nature and Property of Soils. Macmillan Publishing Co., Inc. New York, N.Y.

Brenner, Walter and Barry Rugg. 1982. Exploratory Studies on the Encapsulation of Selected Hazardous Wastes with Sulfur Asphalt Blends. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 315-326.

Burns, J., and G. Karpinski. August 1980. Water Balance Method Estimates How Much Leachate Site Will Produce. Solid Wastes Management. pp. 54-86.

Chou, Sheng-Fu J., Robert A. Griffin, and Mei-In M. Chou. 1982. Effect of Soluble Salts and Caustic Soda on Solubility and Adsorption of Hexachlorocyclopentadiene. Proceedings of the Eighth Annual Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 137-149.

D'Appolonia, D.J. and C.R. Ryan. 1979. Soil-Bentonite Slurry Trench Cutoff Walls. In: Geotechnical Exhibition and Technical Conference Proceedings, Engineered Construction International, Inc., Chicago, IL.

Dragun, James and Charles S. Helling. 1982. Soil and Clay Catalyzed Reaction: I. Physicochemical and Structural Relationships of Organic Chemicals Undergoing Free - Radical Oxidation. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 106-121.

Falco, J.W., L.A. Mulkey, R.R. Swank, Jr., R.E. Lipcsei, and S.M. Brown. A Screening Procedure for Assessing the Transport and Degradation of Solid Waste Constituents in Subsurface and Surface Waters. (Unpublished paper)

Fenn, D.G., K.J. Hanley, and T.V. Degeare. 1975. Use of the Water Balance Method for Predicting Leachate Generation from Solid Waste Disposal Sites. EPA/530/SW-168, Solid Waste Information, U.S. Environmental Protection Agency. Cincinnati, OH. 40 pp.

Freeze, R.A. and J.A. Cherry. 1979. Groundwater. Prentice-Hall, Inc., Englewood Cliffs, N.J. 604 pp.

Fuller, W.H. 1982. Methods for Conducting Soil Column Tests to Predict Pollution Migration. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 87-105.

Garrett, B.C., J.S. Warner, M.P. Miller, and L.G. Taft. 1982. Laboratory and Field Studies of Factors in Predicting Site Specific Composition of Hazardous Waste Leachate. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 67-86.

Gibson, A.C. and P.G. Malone. 1982. Verification of the U.S. EPA HSSWDS Hydrologic Simulation Model. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 13-25.

Giroud, J.P. and J.S. Goldstein. 1982. Geomembrane Liner Design. Waste Age, September 1982.

Glaubinger, R.S., P.M. Kohn, and R. Ramirez. 1979. Love Canal Aftermath: Learning from a Tragedy. Chemical Engineering. October 22.

Guerero, P., November 1982. Personal Communication.

Hardcastle, J.H. and J.K. Mitchell. 1974. Electrolyte Concentration Permeability Relations in Sodium Illite-Silt Mixtures. Clays and Clay Minerals. 22(2):143-154. As cited in Haxo, et al., 1980.

Haxo, H.E. et al. September 1980. Lining of Waste Impoundment and Disposal Facilities. EPA/530/SW-870c, U.S. Environmental Protection Agency, Cincinnati, OH. 385 pp.

Haxo, H.E., Jr. 1981. Testing Materials for Use in the Lining of Waste Disposal Facilities, Hazardous Solid Waste Testing: First Conference. ASTM STP 760, American Society for Testing and Materials. pp. 269-292.

Haxo, H.E. 1982. Effects on Liner Materials of Long-Term Exposure in Waste Environments. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 191-211.

Huck, P.J. 1982. Assessment of Time Domain Reflectometry and Acoustic Emission Monitoring; Leak Detection Systems for Landfill Liners. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 261-273.

Hughes, J. 1975. Use of Bentonite as a Soil Sealant for Leachate Control in Sanitary Landfills. Soil Lab. Eng. Report Data 280-E. American Colloid Co., Skokie, IL. As cited in Haro et al., 1980.

Hung, Cheng Y. 1980. A Model to Simulate Infiltration of Rainwater Through the Cover of a Radioactive Waste Trench Under Saturated and Unsaturated Conditions. Draft submitted to AGU for "Role of the Unsaturated Zone in Radioactive and Hazardous Waste Disposal," to be published by the Ann Arbor Science Publishers in 1983.

ICF Incorporated, Clement Associates, Inc., and SCS Engineers, Inc., 1982. RCRA Risk/Cost Policy Model Project, Phase 2 Report. Submitted to: Office of Solid Waste, U.S. Environmental Protection Agency, June 15, 1982. Draft internal agency document.

JRB Associates, Inc. 1982. Techniques for Evaluating Environmental Processes Associated with the Land Disposal of Specific Hazardous Materials, EPA Contract No. 68-01-5052, DOW No. 36, Task 1.

Kinman, Riley N., Janet I. Rickabaugh, James J. Walsh, and W. Gregory Vogt. 1982. Leachate from Co-Disposal of Municipal and Hazardous Waste in Landfill Simulators. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 274-293.

Krisel, W.J., Jr., Editor. 1980. CREAMS, a Field Scale Model for Chemical Runoff and Erosion from Agricultural Management Systems. Vols. I, II, and III. Draft copy. USDA-SEA, AR, Cons. Res. Report 24.

Kumar, J. and J.A. Jedlicka. 1973. Selecting and Installing Synthetic Pond Linings. Chemical Engineering, February 5, 1973.

Lee, J. 1974. Selecting Membrane Pond Liners. Pollution Engineering. 6(1):33-40.

Lentz, J.J. 1981. Apportionment of Net Recharge in Landfill Covering Layer into Separate Components of Vertical Leakage and Horizontal Seepage. Vol. 17, No. 4, Water Resources Research, American Geophysical Union. pp. 1231-1234.

Lu, J.C.S., R.D. Morrison, and R.J. Stearns. Leachate Production and Management from Municipal Landfills: Summary and Assessment. Calscience Research, Inc. (Unpublished paper)

Lyman, W.J., W.F. Reehl, and D.H. Rosenblatt. 1982. Handbook of Chemical Property Estimation Methods: Environmental Behavior of Organic Compounds. Prepared by Arthur D. Little, Inc. for the U.S. Army Bioengineering Research and Development Laboratory, Fort Detrick, MD. As cited in JRB Associates, 1982.

Mabey, W. and T. Mill. 1978. Critical Review of Hydrolysis of Organic Compounds in Water Under Environmental Conditions. J. Phys. and Chem. 1(2):383, 1978. As cited in JRB Associates, 1982.

Mielenz, R.C. and M.E. King. 1955. Physical-Chemical Properties and Engineering Performance of Clays. Bulletin 169. California Division of Mines. pp. 196-254. As cited in Haxo, et al., 1980.

Mingelgren, U. et al. 1977. A Possible Model for the Surface-Induced Hydrolysis of Organophosphorus Pesticides on Kaolinite Clays, Soil Science Society of America J. 41. As cited in JRB Associates, 1982.

Mill, T. 1980. Data Needed to Predict the Environmental Fate of Organic Chemicals. In: Dynamics, Exposure and Hazard Assessment of Toxic Chemicals. Rizwanul and Hague, Eds. As cited in JRB Associates, 1982.

Montague, P. 1982. Hazardous Waste Landfills: Some Lessons from New Jersey. Civil Engineering. ASCE. September 1982.

Moore, C.A. September 1980. Landfill and Surface Impoundment Performance Evaluation. SW-869, U.S. Environmental Protection Agency, Cincinnati, OH. 63 pp.

Moore, C.A. and M. Roulier. 1982. Evaluating Landfill Containment Capability. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 174-178.

Moore, C.A. and E.M. Ali. 1982. Permeability of Cracked Clay Liners. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 174-178.

Perrier, E.R., and A.C. Gibson. September 1980. Hydrologic Simulation of Solid Waste Disposal Sites. EPA/530/SW-868c, U.S. Environmental Protection Agency, Cincinnati, OH. 111 pp.

Peters, W.R., D.W. Shultz, and B.M. Duff. 1982. Electrical Resistivity Techniques for Locating Liner Leaks. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 250-260.

Pohland, Frederick G., Joseph P. Gould, R. Elizabeth Ramsey, and Daniell C. Walters. 1982. The Behavior of Heavy Metals During Landfill Disposal of Hazardous Wastes. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Wastes. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 360-371.

Pope-Reid Associates, Inc. 1982. Hazardous Waste Landfill Design, Cost and Performance Modelling. Unpublished draft report.

Prickett, T.A. July 1982. Personal Communication.

Rosenbaum, M.S. 1976. Effect of Compaction on the Pore Fluid Chemistry of Montmorillonite. Clays and Clay Minerals. 24:118-121. As cited in Haxo, et al., 1980.

SCS Engineers, Inc. 1982. Release Rate Computations for Land Disposal Facilities. Currently under development for EPA.

Shuckrow, Alan J. and Andrew P. Pajak. 1982. Studies on Leachate and Groundwater Treatment at Three Problem Sites. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 346-359.

Shultz, David W. and Michael Miklas. 1982. Procedures for Installing Liner Systems. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 224-238.

Silka, L.R., and R.L. Swearingen. 1978. A Manual for Evaluating Contamination Potential of Surface Impoundments. EPA-570/9-78-003; U.S. Environmental Protection Agency, Cincinnati, OH. 73 pp.

Skaggs, R.W. 1980. Combination Surface-Subsurface Drainage System for Humid Regions. Journal of the Irrigation and Drainage Division, ASCE, Vol. 106, No. 1R4, Proc. Paper 15883, pp. 265-283.

Skaggs, R.W. 1980. A Water Management Model for Artificially Drained Soils. Tech. Bul. No. 267, North Carolina Agricultural Research Service. 54 pp.

Skaggs, R.W. 1982. Modification to DRAINMOD to Consider Drainage from and Seepage Through a Landfill. I. Documentation. Unpublished EPA Document, August 26, 1982.

Skaggs, R.W., A. Nassehzadeh-Tabrizi, and G.R. Foster. 1982. Subsurface Drainage Effects on Erosion. Paper No. 8212, Journal Series, North Carolina Agricultural Research Service, Raleigh. pp. 167-172.

Skaggs, R.W., N.R. Fausey, and B.H. Nolte. 1981. Water Management Model Evaluation for North Central Ohio. 0001-2351/81-2404-0929, American Society of Agricultural Engineers. pp. 922-928.

Skaggs, R.W., and J.W. Gillian. 1981. Effect of Drainage System Design and Operation on Nitrate Transport. 0001-2351/81-2404-0929, American Society of Agricultural Engineers. pp. 929-940.

Skaggs, R.W. 1982. Field Evaluation of a Water Management Simulation Model. 0001-2351/82/2503-0666, American Society of Agricultural Engineers. pp. 666-674.

Spooner, P.S., et al. 1982. Draft Technical Handbook on Slurry Trench Construction for Pollution Migration Control. EPA Contract No. 68-01-3113.

Thornthwaite, C.W. and J.R. Mather. 1955. The Water Balance. Centerton, N.J. 104 p. (Drexel Institute of Technology. Laboratory of Climatology. Publications in Climatology, V. 8, No. 1.) As cited in Fenn, Hanley, and DeGeare, 1975.

Thornthwaite, C.W. and J.R. Mather. 1957. Instructions and Tables for Computing Potential Evapotranspiration and the Water Balance. Centerton, NJ. pp. 185-311. (Drexel Institute of Technology. Laboratory of Climatology. Publications in Climatology, V. 10, No. 3.) As cited in Fenn, Hanley, and DeGeare, 1975.

Tolman, A.L., A.P. Ballesteros, Jr., W.H. Beck, Jr., and G.H. Emrich. 1978. Guidance Manual for Minimizing Pollution from Waste Disposal Sites, EPA-600/2-78-142. U.S. Environmental Protection Agency, Cincinnati, OH. 83 pp.

U.S. Environmental Protection Agency. 1981. Land Disposal of Hazardous Waste: Summary of Panel Discussions, (SW-947). U.S. EPA, Washington, D.C., May 18-22, 1981. Contract No. 68-01-6092.

U.S. Environmental Protection Agency. June 1982. Post-Closure Liability Trust Fund Model Development. Unpublished internal report.

U.S. Environmental Protection Agency. 1982. Hazardous Waste Management System: Permitting Requirements for Land Disposal Facilities, (40 CFR Parts 122, 260, 264, and 265). Federal Register, Vol. 47, No. 143, July 26, 1982.

Waller, Muriel Jennings and J.L. Davis. 1982. Assessment of Techniques to Detect Liner Failings. Proceedings of the Eighth Annual Research Symposium: Land Disposal of Hazardous Waste. EPA-600/9-82-002; U.S. Environmental Protection Agency, Cincinnati, OH. pp. 239-249.

Weber, W.J. 1972. Physiochemical Processes for Water Quality Control. As cited in JRB Associates, 1982.

Wong, J. 1977. The Design of a System for Collecting Leachate from a Lined Landfill Site. Water Resources Research, V. 13, No. 2, pp. 404-410. As cited in Moore, 1980.

7.4.2 Transport Models

Anderson, M.P. 1981. Groundwater Quality Models - State of the Art. In Proceedings and Recommendations of the Workshop on Groundwater Problems in the Ohio River Basin. Cincinnati, OH. pp. 90-96.

Anderson, M.P. 1979. Using Models to Simulate the Movement of Contaminants through Groundwater Flow Systems. CRC Critical Reviews in Environmental Control 9(2):97-156.

Bachmat, Y., J. Bredehoeft, B. Andrews, D. Holtz, and S. Sebastian. 1980. Groundwater Management: The Use of Numerical Models. Water Resources Monograph 5. American Geophysical Union, Washington, D.C. 127 p.

Bachmat, Y., B. Andrews, D. Holt, and S. Sebastian. 1978. Utilization of Numerical Groundwater Models for Water Resources Management. Robert S. Kerr Environmental Research Laboratory, U.S. EPA, EPA-600/8-78-012.

Battelle Pacific Northwest Laboratories. 1982. Personal communication.

Bibby, R. 1981. Mass Transport of Solutes in Dual-Porosity Media. Water Resources Research 17(4):1075-1081.

Bonazountas, M. and J. Wagner. 1981. "SESOIL": A Seasonal Soil Compartment Model. Arthur D. Little, Inc., Cambridge, MA.

Chang, S., K. Barrett, S. Haus, and A. Platt. 1981. Site Ranking Model for Determining Remedial Action Priorities Among Uncontrolled Hazardous Substances Facilities. The MITRE Corporation, Working Paper to EPA, Contract No. 68-01-6278.

Charbeneau, R.J. 1981. Groundwater Contamination Transport with Adsorption and Ion Exchange Chemistry: Method of Characteristics for Case Without Dispersion. Water Resources Research 17(3):705-713.

Chou, S.J., B.W. Fischer, and R.A. Griffin. 1981. Aqueous Chemistry and Adsorption of Hexachlorocyclopentadiene by Earth materials. In: Proceedings of the Seventh Annual Research Symposium on Land Disposal of Hazardous Waste. EPA-600/9-81-0026, p. 29-42.

Chu, S. and G. Sposito. 1980. A Derivation of the Macroscopic Solute Transport Equation for Homogeneous, Saturated, Porous Media. Water Resources Research 16(3):542-546.

Cleary, R. 1982. Personal communication.

Dettinger, M.D. and J.L. Wilson. 1981. First Order Analysis of Uncertainty and Numerical Models of Groundwater Flow. Part 1. Mathematical Development. Water Resources Research 17(1):149-161.

Dragun, J. and C.S. Helling. 1981. Evaluation of Molecular Modeling Techniques to Estimate the Mobility of Organic Soils: II. Water Solubility and the Molecular Fragment Mobility Coefficient. In: Proceedings of the Seventh Annual Research Symposium on Land Disposal of Hazardous Waste. EPA-600/9-81-0026, p. 58-70.

Duffy, J.J., E. Peake, and M.F. Mohtadi. 1980. Oil Spills on Land as Potential Sources of Groundwater Contamination. Environment International 3(2):107-120.

Enfield, C.G., R.F. Carsel, S.Z. Cohen, T. Phan, and D.M. Walters. 1982. Approximating Pollutant Transport to Ground Water. U.S. EPA. RSKERL. Ada, OK. (Unpublished paper)

Falco, J.W., L.A. Mulkey, R.R. Swank, R.E. Lipcsei, and S.W. Brown. A Screening Procedure for Assessing the Transport and Degradation of Solid Waste Constituents in Subsurface and Surface Waters. (Unpublished paper)

Faust, C.R. The Use of Modeling in Monitoring Network Design. Unpublished

Fenn, D.G., K.J. Hanley, and T.V. Degeare. 1975. Use of the Water Balance Method for Predicting Leachate Generation from Solid Waste Disposal Sites. EPA/530/SW-168. U.S. EPA, Office of Solid Waste, Cincinnati, OH.

Fuller, W.H. 1982. Methods for Conducting Soil Column Tests to Predict Pollutant Migration. In: Proceedings of the the Eighth Annual Research Symposium on Land Disposal of Hazardous Waste. EPA/600/9-82-002, p. 87-103.

Fuller, W.H. 1977. Movement of Selected Metals, Asbestos, and Cyanide in Soil: Applications to Waste Disposal Problems. MERL, ORD, U.S. EPA, EPA/600/2-77-020. 243 p.

Fuller, W.H., A. Amoozegar-Fard, E. Niebla, and M. Boyle. 1981. Behavior of Cd, Ni, and Zn in Single and Mixed Combinations in Landfill Leachates. In: Proceedings of the Seventh Annual Research Symposium on Land Disposal of Hazardous Waste. EPA/600/9-81-0026, p. 18-28.

Gorelick, S.M. and I. Remson. 1982. Optimal Dynamic Management of Groundwater Pollutant Sources. Water Resources Research 18(1):71-76.

Grisak, G.E. and J.F. Pickens. 1980. Solute Transport through Fractured Media. 1. The Effect of Matrix Diffusion. Water Resources Research 16(4):719-730.

Grisak, G.E., J.F. Pickens, and J.A. Cherry. 1980. Solute Transport through Fractured Media. 2. Column Study of Fractured Till. Water Resources Research 16(4):731-739.

Golder Associates. 1982. Personal Communication.

Grove, D.B. 1977. The Use of Galerkin Finite-Element Methods to Solve Mass-Transport Equations. USGS, Water Resource Division, Denver, CO. USGS/WRI-77-49.

Hague, R. 1980. Dynamic Exposure and Hazard Assessment of Toxic Chemicals. Ann Arbor Science Publishers, Inc. 496 pp.

Haxo, H., Jr., S. Dakeasian, M. Fong, and R. White. 1980. Lining of Waste Impoundment and Disposal Facilities. U.S. EPA, MERL, Cincinnati, OH.

Intercomp Resource Development and Engineering, Inc. 1978. A Model for Calculating Effects of Liquid Waste Disposal in Deep Saline Aquifer. Part I - Development. Part II - Documentation. USGS, Water Resources Division, Reston, VA.

Jones, C.J. 1978. The Ranking of Hazardous Materials by Means of Hazard Indices. Journal of Hazardous Materials 2:363-389.

Jury, W.A. 1982. Simulation of Solute Transport Using a Transfer Function Model. Water Resources Research 18(2):363-368.

Kent, D.C., W.A. Pettyjohn, F. Witz, and T. Prickett. 1982. Prediction of Leachate Plume Migration and Mixing in Ground-Water. Solid and Hazardous Waste Research and Development Annual Symposium Proceedings, pp. 71-82.

Khaleel, R. and D.L. Reddell. 1977. Simulation of Pollutant Movement in Groundwater Aquifers. Technical Report No. 81. Texas Water Resources Institute, Texas A&M University.

Konikow, L.F. and J.D. Bredehoeft. 1974. Computer Model of Two-Dimensional Solute Transport and Dispersion in Groundwater. In: Techniques of Water Resource Investigation. Book 7, Chapter C2.

Krisel, W.J., Jr., Editor. 1980. CREAMS, A Field Scale Model for Chemical Runoff and Erosion from Agricultural Management Systems. Vols. I, II and III. Draft copy. USDA-SEA, AR, Cons. Res. Report 24.

- Kuczera, G. 1982. On the Relationship Between the Reliability of Parameter Estimates and Hydrologic Time Series Data Used In Calibration. *Water Resources Research* 18(1):146-154.
- Larson, N.M. and M. Reeves. 1979. ODMOD. Union Carbide Corp., Nuclear Division. Oak Ridge, TN.
- LeGrand, H.E. 1964. System for Evaluation of Contamination Potential of Some Waste Disposal Sites. *Journal of the American Water Works Association* 56(8):959-967, 969-970, 974.
- Lentz, J.L. 1981. Apportionment of Net Recharge in Landfill Covering Layer into Separate Components of Vertical Leakage and Horizontal Seepage. *Water Resources Research* 17(4):1231-1234.
- Maslia, M.L. and R.H. Johnston. 1982. Simulation of Groundwater Flow in the Vicinity of Hyde Park Landfill, Niagara Falls, New York. USGS Open File Report 82-159.
- Mercer, J.W. and C.R. Faust. 1981. Ground-Water Modeling. National Water Well Association. 60 p.
- Moore, C.A. 1980. Landfill and Surface Impoundment Performance Evaluation Manual. U.S. EPA, Office of Water and Waste Management, Washington, D.C. SW-869. 63 p.
- Nelson, R.W. and J.A. Schur. 1980. Assessment of Effectiveness of Geologic Oscillation Systems: PATHS Groundwater Hydrologic Model. Battelle, Pacific Northwest Laboratory, Richland, WA.
- Perrier, E.R. and A.C. Gibson. 1980. Hydrologic Simulation on Solid Waste Disposal Sites (HSSWDS). U.S. EPA, MERL, ORD. SW-868. 111 p.
- Pettyjohn, W.A., T.A. Prickett, D.C. Kent, and H.E. LeGrand. 1981. Prediction of Leachate Plume Migration. In: Proceedings of the Seventh Annual Research Symposium on Land Disposal of Hazardous Waste. EPA/600/9-81-0026. p. 71-84.
- Pickens, J.F. and G.E. Grisak. 1981. Modeling of Scale-Dependent Dispersion in Hydrogeologic Systems. *Water Resources Research* 17(6):1701-1711.
- Pickens, J.R. and W.C. Lennox. 1976. Numerical Simulation of Waste Movement in Steady Groundwater Flow Systems. *Water Resources Research* 12(2):171-180.
- Pope-Reid Associates, Inc. 1982. Leachate Travel Time Model. (Unpublished)

- Pope-Reid Associates, Inc. 1982. Technical Review of Groundwater Models. Office of Solid Waste, U.S. EPA, Washington, D.C. 28 p.
- Prickett, T.A. 1981. Mathematical Modeling Techniques for Groundwater Management. In: Proceedings and Recommendations of the Workshop on Groundwater Problems in the Ohio River Basin, Cincinnati, Ohio. April 28-29, 1981. p. 97-104.
- Prickett, T.A., T.G. Naymik, and C.G. Lonnquist. 1981. A "Random Walk" Solute Transport Model for Selected Groundwater Quality Evaluations. Illinois State Water Survey, Bulletin 65.
- Rao, P.V., K.M. Portier, and P.S.C. Rao. 1981. A Stochastic Approach for Describing Connective-Dispersive Solute Transport in Saturated Porous Media. Water Resources Research 17(4):963-968.
- Ross, B. and C.M. Koplik. 1978. A Statistical Approach to Modeling Transport of Pollutants in Groundwater. Journal of the International Association for Mathematical Geology 10(6):657-672.
- Sagar, B. and A. Runcal. 1982. Permeability of Fractured Rock: Effect of Fracture Size and Data Uncertainties. Water Resources Research 18(2):266-274.
- Science Applications, Inc. 1981. System Analysis of Shallow Land Burial. Science Applications, Inc., McLean, VA. NUREG-CR-1963.
- Schnoor, J.L. 1981. Assessment of the Exposure, Fate and Persistence of Toxic Organic Chemicals to Aquatic Ecosystems in Stream and Lake Environments. Lecture Notes for Water Quality Assessment of Toxic and Conventional Pollutants in Lakes and Streams Sponsored by U.S. EPA (R&D). Arlington, VA.
- SCS Engineers, Inc. 1982. Release Rate Model. Currently under development for EPA.
- Siefken, D.L. and R.J. Starmer. 1982. NRC-Funded Studies on Waste Disposal in Partially Saturated Media. AGU Spring Meeting, 4 June 1982.
- Silka, L.R. and T.L. Sweringen. 1978. A Manual for Evaluating Contamination Potential of Surface Impoundments. U.S. EPA, Groundwater Protection Branch. EPA/570/9-78-003. 73 p.
- Smith, L. and F.W. Schwartz. 1980. Mass Transport. 1. A Stochastic Analysis of Macroscopic Dispersion. Water Resources Research 16(2):303-313.
- Smith, L. and F.W. Schwartz. 1981. Mass Transport. 2. Analysis of Uncertainty in Prediction. Water Resources Research 17(2):351-369.

Smith, L. and F.W. Schwartz. 1981. Mass Transport. 3. Role of Hydraulic Conductivity Data in Prediction. Water Resources Research 17(5):1463-1479.

Sykes, J.F., S. Soyupak, and G.J. Farquhar. 1982. Modeling of Leachate Organic Migration and Attenuation in Groundwater Below Sanitary Landfills. Water Resources Research 18(1):135-145.

Tang, D.H., E.O. Frind, and E.A. Sudicky. 1981. Contaminant Transport in Fractured Porous Media: Analytical Solution for a Single Fracture. Water Resources Research 17(3):555-564.

Tang, D.H., F.W. Schwartz, and L. Smith. 1982. Stochastic Modeling of Mass Transport in a Random Velocity Field. Water Resources Research 18(2) 231-244.

U.S. EPA. 1982. Post-Closure Liability Trust Fund Model Development. Personal communication.

Van Genuchten, M.T., G.F. Pinder, and W.P. Saukin. 1977. Modeling of Leachate and Soil Interactions in an Aquifer. Proceedings of the Third Annual Municipal Solid Waste Research Symposium on Management of Gas and Leachate in Landfills. EPA/600/9-77-026. p. 95-103.

Wagner, J. 1982. Personal communication.

Weston, R.F. 1978. Pollution Prediction Techniques - A State-of-the-Art Assessment. U.S. EPA, Office of Solid Waste. EPA/513/684-8491.

Wilson, J.L. and L.W. Gelhan. 1981. Analysis of Longitudinal Dispersion in Unsaturated Flow. 1. The Analytical Method. Water Resources Research 17(1):122-130.

Wilson, J.T., C.G. Enfield, W.J. Dunlap, R.L. Cosby, D.A. Foster, and L.B. Baskin. 1982. Transport and Fate of Selected Organic Pollutants in a Sandy Soil. U.S. EPA, RSKERL, Ada, OK. (Unpublished report)

Wyrick, G.G. and J.W. Borchers. 1982. Hydrologic Effects of Stress-Relief Fracturing in an Appalachian Valley. USGS Water Supply Paper 2177.

Yeh, G.T. 1981. AT123D:Analytical Transient One-, Two-, and Three-Dimensional Simulation of Waste Transport in the Aquifer System. Oak Ridge National Laboratory, Environmental Science Division. Publication No. 1439. ORNL-5601. 83 pp.

Yeh, G.T. and D.S. Ward. 1981. FEMWASTE: A Finite-Element Model of Waste Transport Through Saturated-Unsaturated Porous Media. Oak Ridge National Laboratory, Environmental Science Division. Publication No. 1462. ORNL-5601. 137 p.

Yeh, G.T. and D.S. Ward. 1980. FEMWATER: A Finite-Element Model of Water Flow Through Saturated-Unsaturated Porous Media. Oak Ridge National Laboratory, Environmental Science Division. Publication No. 1370. ORNL-5567. 153 p.